

PCT

WORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau



48

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁶ : C12N 15/88, A61K 48/00, 9/127		A2	(11) International Publication Number: WO 96/40964
			(43) International Publication Date: 19 December 1996 (19.12.96)
(21) International Application Number: PCT/US96/09949		<p>ter [US/CA]; Apartment 301, 2664 Birch Street, Vancouver, British Columbia V6H 2T5 (CA).</p> <p>(74) Agents: KEZER, William, B. et al.; Townsend and Townsend and Crew L.L.P., Two Embarcadero Center, San Francisco, CA 94111-3834 (US).</p> <p>(81) Designated States: AL, AM, AT, AU, AZ, BB, BG, BR, BY, CA, CH, CN, CZ, DE, DK, EE, ES, FI, GB, GE, HU, IL, IS, JP, KE, KG, KP, KR, KZ, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, TJ, TM, TR, TT, UA, UG, US, UZ, VN, ARIPO patent (KE, LS, MW, SD, SZ, UG), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).</p> <p>Published Without international search report and to be republished upon receipt of that report.</p>	
(22) International Filing Date: 6 June 1996 (06.06.96)			
(30) Priority Data: 08/484,282 7 June 1995 (07.06.95) US 08/485,458 7 June 1995 (07.06.95) US			
(71) Applicant (for all designated States except US): INEX PHARMACEUTICALS CORPORATION [CA/CA]; 1779 West 75th Avenue, Vancouver, British Columbia V6P 6P2 (CA).			
(72) Inventors; and (75) Inventors/Applicants (for US only): WHEELER, Jeffery, J. [US/CA]; 306 - 1340 W. 70th Avenue, Vancouver, British Columbia V6P 2Y8 (CA). BALLY, Marcel, B. [US/CA]; SPC 11 Harding Road, Bowen Island, British Columbia V0N 1G0 (CA). ZHANG, Yuan-Peng [CN/CA]; Suite 105, 40 East 11th Avenue, Vancouver, British Columbia V5T 2B8 (CA). REIMER, Dorothy, L. [US/CA]; Suite 202, 55 East 12th Avenue, Vancouver, British Columbia V5T 4J4 (CA). HOPE, Michael [US/CA]; 3550 West 11th Avenue, Vancouver, British Columbia V6R 2K2 (CA). CULLIS, Pieter, R. [US/CA]; 3732 West 1st Avenue, Vancouver, British Columbia V6R 1H4 (CA). SCHERRER, Pe-			
(54) Title: LIPID-NUCLEIC ACID PARTICLES PREPARED VIA A HYDROPHOBIC LIPID-NUCLEIC ACID COMPLEX INTERMEDIATE AND USE FOR GENE TRANSFER			
(57) Abstract			
<p>Novel lipid-nucleic acid particulate complexes which are useful for <i>in vitro</i> or <i>in vivo</i> gene transfer are described. The particles can be formed using either detergent dialysis methods or methods which utilize organic solvents. Upon removal of a solubilizing component (i.e., detergent or an organic solvent) the lipid-nucleic acid complexes form particles wherein the nucleic acid is serum-stable and is protected from degradation. The particles thus formed have access to extravascular sites and target cell populations and are suitable for the therapeutic delivery of nucleic acids.</p>			

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AM	Armenia	GB	United Kingdom	MW	Malawi
AT	Austria	GE	Georgia	MX	Mexico
AU	Australia	GN	Guinea	NE	Niger
BB	Barbados	GR	Greece	NL	Netherlands
BE	Belgium	HU	Hungary	NO	Norway
BF	Burkina Faso	IE	Ireland	NZ	New Zealand
BG	Bulgaria	IT	Italy	PL	Poland
BJ	Benin	JP	Japan	PT	Portugal
BR	Brazil	KE	Kenya	RO	Romania
BY	Belarus	KG	Kyrgyzstan	RU	Russian Federation
CA	Canada	KP	Democratic People's Republic of Korea	SD	Sudan
CF	Central African Republic	KR	Republic of Korea	SE	Sweden
CG	Congo	KZ	Kazakhstan	SG	Singapore
CH	Switzerland	LJ	Liechtenstein	SI	Slovenia
CI	Côte d'Ivoire	LK	Sri Lanka	SK	Slovakia
CM	Cameroon	LR	Liberia	SN	Senegal
CN	China	LT	Lithuania	SZ	Swaziland
CS	Czechoslovakia	LU	Luxembourg	TD	Chad
CZ	Czech Republic	LV	Latvia	TG	Togo
DE	Germany	MC	Monaco	TJ	Tajikistan
DK	Denmark	MD	Republic of Moldova	TT	Trinidad and Tobago
EE	Estonia	MG	Madagascar	UA	Ukraine
ES	Spain	ML	Mali	UG	Uganda
FI	Finland	MN	Mongolia	US	United States of America
FR	France	MR	Mauritania	UZ	Uzbekistan
GA	Gabon			VN	Viet Nam

LIPID-NUCLEIC ACID PARTICLES PREPARED VIA A HYDROPHOBIC LIPID-NUCLEIC ACID COMPLEX INTERMEDIATE AND USE FOR GENE TRANSFER

This application is a continuation-in-part of U.S. application serial no. 08/485,458 and of U.S. application serial no. 08/484,282, both filed on June 7, 1995.

FIELD OF THE INVENTION

This invention relates to lipid-nucleic acid particles which are useful for the introduction of nucleic acids into cells, and methods of making and using them. The invention provides a circulation-stable, characterizable delivery vehicle for the introduction of plasmids or antisense compounds into cells. These vehicles are safe,
5 stable, and practical for clinical use.

BACKGROUND OF THE INVENTION

Gene transfer into genetically impaired host cells in order to correct the genetic defects has vast potential for successfully treating a variety of thus far hitherto untreatable medical conditions. There are currently six major non-viral methods by
10 which genes are introduced into host cells: (i) direct microinjection, (ii) calcium phosphate precipitation, (ii) DEAE-dextran complexes, (iv) electroporation, (v) cationic lipid complexes and (vi) reconstituted viruses and virosomes (see Chang, *et al.*, *Focus* 10:88 (1988)).

Most reported examples of gene transfer have been performed *in vitro*. *In vivo* gene transfer is complicated by serum interactions, immune clearance, enzymatic degradation of the genes, toxicity and biodistribution. In *in vivo* administration, selection is not possible, and a reasonably high frequency of transformation is necessary to achieve sufficient expression to compensate for a defective endogenous gene.

The *in vivo* gene transfer methods under study in the clinic consist almost
20 entirely of viral vectors. Although viral vectors have the inherent ability to transport nucleic acids across cell membranes and some can integrate exogenous DNA into the

chromosomes, they can carry only limited amounts of DNA. In addition, their use poses significant risks. One such risk is that the viral vector may revert to a pathogenic genotype either through mutation or genetic exchange with a wild type virus.

In view of these limitations and risks, alternative non-viral-based gene transfer methods have been developed. These methods use often plasmid vectors, which are small circular sequences of DNA, as vectors for DNA delivery. However, most plasmids do not possess the attributes required for intracellular delivery and therefore sophisticated delivery systems are required.

Cationic lipid complexes are presently the most effective generally used means of introducing non-viral nucleic acids into cells. A number of different formulations incorporating cationic lipids are commercially available. These include: (i) LIPOFECTIN® (which uses 1,2-dioleoyloxy-3-(N,N,N-trimethylamino)propane chloride, or DOTMA, see Eppstein, *et al.*, U.S. Patent No. 4,897,355); LIPOFECTAMINE® (which uses DOSPA, see Hawley-Nelson, *et al.*, Focus 15(3):73 (1993)); and LIPOFECTACE® (which uses N,N-distearyl-N,N-dimethyl-ammonium bromide, or DDAB, see Rose, U.S. Patent No. 5,279,833). Others have reported alternative cationic lipids that work in essentially the same manner but with different efficiencies, for example 1,2-dioleoyloxy-3-(N,N,N-trimethylamino) propane chloride, or DOTAP (see Stomatatos, *et al.*, Biochemistry 27: 3917-3925 (1988)); glycerol based lipids (see Leventis, *et al.*, Biochem. Biophys. Acta 1023:124 (1990); lipopolyamines (see, Behr, *et al.*, U.S. Patent No. 5,171,678) and cholesterol based lipids (see Epan, *et al.*, WO 93/05162, and U.S. Patent No. 5,283,185). It has been reported that DOTMA and related compounds are significantly more active in gene transfer assays than their saturated analogues (see, Felgner, *et al.*, WO91/16024). However, both DOTMA and DOSPA based formulations, despite their efficiency in effecting gene transfer, are prohibitively expensive. DDAB on the other hand is inexpensive and readily available from chemical suppliers but is less effective than DOTMA in most cell lines. Another disadvantage of the current lipid systems is that they are not appropriate for intravenous injection.

Lipid-based vectors used in gene transfer have generally been formulated in one of two ways. In one method, the nucleic acid is introduced into preformed liposomes made of mixture of cationic lipids and neutral lipids. The complexes thus formed have undefined and complicated structures and the lipofection efficiency is severely reduced by the presence of serum. A second method involves the formation of DNA complexes with mono- or poly-cationic lipids without the presence of a neutral

lipid. These complexes are often prepared in the presence of ethanol and are not stable in water. Additionally, these complexes are adversely affected by serum (see, Behr, *Acc. Chem. Res.* 26:274-78 (1993)).

5 An examination of the relationship between the chemical structure of the carrier vehicle and its efficiency of gene transfer has indicated that the characteristics which provide for effective gene transfer would make a carrier unstable in circulation (see, Ballas, *et al.*, *Biochim. Biophys. Acta* 939:8-18 (1988)). Additionally, degradation either outside or inside the target cell remains a problem (see, Duzghines, *Subcellular Biochemistry* 11:195-286 (1985)). Others who have attempted to encapsulate DNA in
10 lipid-based formulations have not overcome these problems (see, Szoka *et al.*, *Ann. Rev. Biophys. Bioeng.* 9:467 (1980); Deamer, *U.S. Patent No. 4,515,736*, and Legendre, *Pharm. Res.* 9:1235-1242 (1992)).

Ideally, a delivery vehicle for a nucleic acid or plasmid will have the following characteristics: a) ease of preparation, b) capable of carrying a large amount of
15 DNA per particle to enable gene transfer of all sizes of genes and reduce the volume of injection, c) homogenous, d) reproducible, e) is serum stable with minimal serum interactions and shields DNA from extracellular degradation, and f) is capable of transfecting target cells in such a way that the DNA is not digested intracellularly.

The present invention provides such compositions and methods for their
20 preparation and use.

SUMMARY OF THE INVENTION

The present invention comprises novel, lipid-nucleic acid particles. The invention also comprises methods of making and using these particles.

25 In some embodiments, the particles are made by formation of hydrophobic intermediate complexes in either detergent-based or organic solvent-based systems, followed by removal of the detergent or organic solvent. Preferred embodiments are charge-neutralized.

In one embodiment, a plasmid is combined with cationic lipids in a detergent solution to provide a coated plasmid-lipid complex. The complex is then
30 contacted with non-cationic lipids to provide a solution of detergent, a plasmid-lipid complex and non-cationic lipids, and the detergent is then removed to provide a solution of serum-stable plasmid-lipid particles, in which the plasmid is encapsulated in a lipid

bilayer. The particles thus formed have a size of about 50-150 nm.

In another embodiment, serum-stable plasmid-lipid particles are formed by preparing a mixture of cationic lipids and non-cationic lipids in an organic solvent; contacting an aqueous solution of plasmid with the mixture of cationic and non-cationic
5 lipids to provide a clear single phase; and removing the organic solvent to provide a suspension of plasmid-lipid particles, in which the plasmid is encapsulated in a lipid bilayer, and the particles are stable in serum and have a size of about 50-150 nm.

Another method of forming lipid-nucleic acid particles involves:

(a) contacting nucleic acids with a solution of non-cationic lipids and a
10 detergent to form a nucleic acid-lipid mixture;

(b) contacting cationic lipids with the nucleic acid-lipid mixture to neutralize the negative charge of said nucleic acids and form a charge-neutralized mixture of nucleic acids and lipids; and

(c) removing the detergent from the charge-neutralized mixture to provide
15 the lipid-nucleic acid particles in which the nucleic acids are protected from degradation.

Another method of forming lipid-nucleic acid particles involves:

(a) contacting an amount of cationic lipids with nucleic acids in a solution; the solution comprising of from about 15-35% water and about 65-85% organic solvent and the amount of cationic lipids being sufficient to produce a +/- charge ratio of from
20 about 0.85 to about 2.0, to provide a hydrophobic, charge-neutralized lipid-nucleic acid complex;

(b) contacting the hydrophobic, charge-neutralized lipid-nucleic acid complex in solution with non-cationic lipids, to provide a lipid-nucleic acid mixture; and

(c) removing the organic solvents from the lipid-nucleic acid mixture to
25 provide lipid-nucleic acid particles in which the nucleic acids are protected from degradation.

The lipid-nucleic acid particles of the present invention are useful for the therapeutic delivery of nucleic acids. In one embodiment, the particles are constructed via a hydrophobic lipid-nucleic acid intermediate (or complex). Upon removal of a
30 solubilizing component (*i.e.*, detergent or an organic solvent) the nucleic acid becomes protected from degradation. The particles thus formed are suitable for use in intravenous nucleic acid transfer as they are stable in circulation, of a size required for pharmacodynamic behavior resulting in access to extravascular sites and target cell populations.

In particular, it is an object of this invention to provide *in vitro* and *in vivo* methods for treatment of diseases which involve the overproduction or underproduction of particular proteins. In these methods, a nucleic acid encoding a desired protein or blocking the production of an undesired protein, is formulated into a lipid-nucleic acid particle, and the particles are administered to patients requiring such treatment. Alternatively, cells are removed from a patient, transfected with the lipid-nucleic acid particles described herein, and reinjected into the patient.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 illustrates a nucleic acid-lipid particle-mediated gene transfer using "sandwich-type" complexes of DNA.

Figure 2 illustrates an aggregation and precipitation which commonly occurs during the entrapment of large nucleic acids in lipid complexes.

Figure 3 provides a schematic representation of the preparation of plasmid-lipid particles according to certain embodiments of the present invention.

Figure 4 illustrates the recovery of ^3H -DNA from encapsulated particles following the reverse-phase preparation of the particles and extrusion through a 400 nm filter and a 200 nm filter. Lipid composition is POPC:DODAC:PEG-Cer- C_{20} . PEG-Cer C_{20} was held constant at 10 mole% and POPC and DODAC were changed relative to each other. 20 mg lipid; 50 μg plasmid DNA (7.5 kbp).

Figure 5 illustrates the recovery of ^3H -DNA from particles prepared using a reverse-phase procedure. The particles were extruded through a 200 nm filter and eluted on a DEAE Sepharose CL-6B anion exchange column. The percent recovery reported is based on the amount recovered after filtration. Lipid composition is as in Figure 4.

Figure 6 illustrates the recovery of ^{14}C -lipid from encapsulated particles following the reverse-phase preparation of the particles and extrusion through a 400 nm filter and a 200 nm filter. Lipid composition is as in Figure 4.

Figure 7 illustrates the recovery of ^{14}C -lipid from particles prepared using a reverse-phase procedure. The particles were extruded through a 200 nm filter and eluted on a DEAE Sepharose CL-6B anion exchange column. The percent recovery reported is based on the amount recovered after filtration. Lipid composition is as in Figure 4.

Figure 8 illustrates the effect of DODAC concentration on the encapsulation of plasmid DNA. Encapsulation efficiency was measured by anion exchange chromatography. Vesicles were composed of DOPE, DODAC and 10 mole% PEG-Cer-C₂₀ (symbol) or EPC, DODAC and 10 mole% PEG-Cer-C₂₀ (symbol). Total lipid and DNA concentrations were 10 mmole/ml and 50 µg/ml, respectively.

Figures 9A and 9B illustrate the effect of serum nucleases on free pCMVCAT DNA as assessed by column chromatography before (A) and after (B) incubation in 80% mouse serum. Free ³H-DNA (pCMVCAT) was eluted on a Sepharose CL-4B column in HBS, pH 7.4.

Figure 10 illustrates the effect of serum nucleases on encapsulated pCMVCAT DNA (prepared by reverse-phase) as assessed by column chromatography. Sepharose CL-4B column profile of encapsulated pCMV plasmid incubated in 80% mouse serum for 30 min. (A) External DNA was removed by ion exchange chromatography prior to incubation in serum. (B) External DNA was not removed prior to incubation in serum. Lipid composition was POPC:DODAC:PEG-Cer-C₂₀. Total lipid and plasmid concentrations were 20 µmole/ml and 50 µg/ml prior to anion exchange chromatography.

Figures 11A and 11B illustrate the effect of serum nucleases on encapsulated pCMVCAT DNA (prepared by detergent dialysis) as assessed by column chromatography. Sepharose CL-4B column profile of encapsulated pCMV plasmid incubated in 80% mouse serum for 30 min. (A) External DNA was removed by ion exchange chromatography prior to incubation in serum. (B) External DNA was not removed prior to incubation in serum. The lipid composition was DOPE:DODAC:PEG-Cer-C₂₀ (84:6:10). Total lipid and plasmid concentrations were 10 µmole/ml and 400 µg/ml prior to anion exchange chromatography.

Figures 12A and 12B illustrate the resistance of plasmid complexed to preformed liposomes composed of DOPE:DODAC(50:50) (A) and plasmid encapsulated within DOPE:DODAC:PEG-Cer-C₁₄ particles (B) to digestion by DNase I. Plasmid DNA was extracted and subjected to PCR (polymerized chain reaction) to amplify for visualization on a gel. Free plasmid was used as a control. Lane 1: 1 kb DNA marker; Lane 2: PCR negative control (no DNA); Lane 3: free plasmid alone; Lane 4: free plasmid in 0.05% detergent (Triton X-100); Lane 5: free plasmid incubated with DNase I in the absence of detergent; Lane 6: free plasmid incubated with DNase I in the presence of detergent; Lane 7: complexed (A) or encapsulated (B) plasmid alone; Lane

8: complexed (A) or encapsulated (B) plasmid in 0.05% detergent; Lane 9: complexed (A) or encapsulated (B) plasmid incubated in DNase I in the absence of detergent; Lane 10: complexed (A) or encapsulated (B) plasmid incubated in DNase I in the presence of detergent.

5 Figure 13 illustrates the effect of plasmid DNA concentration on encapsulation efficiency (detergent dialysis). Vesicles were composed of DOPE:DODAC:PEG-Cer (84:6:10) at a lipid concentration of 10 μ mole/ml.

 Figure 14 illustrates the effect of NaCl concentration on the optimal DODAC concentration for plasmid entrapment. Lipid composition was
10 DOPE:DODAC:PEG-Cer- C_{14} (or PEG-Cer- C_{20}). PEG-Cer was held constant at 10 mole%. Total lipid concentration was 10 μ mole/ml. Plasmid concentration was 50 μ g/ml.

 Figure 15 illustrates the size distribution of plasmid:lipid particles prepared by the detergent dialysis procedure (Volume weighted analysis). Lipid composition was
15 DOPE:DODAC:PEG-Cer- C_{20} (84:6:10).

 Figure 16 illustrates the size distribution of plasmid:lipid particles prepared by the detergent dialysis procedure (Number weighted analysis). Lipid composition was DOPE:DODAC:PEG-Cer- C_{20} (84:6:10).

 Figures 17A and 17B provide electron micrographs of liposomes composed
20 of DOPE:DODAC:PEO-Cer- C_{20} without encapsulated plasmid (A) and the plasmid:lipid particles (B). The small arrows denote empty liposomes approximately 100 nm in diameter. These are compared to electron-dense particles surrounded by a membrane bilayer (large arrows). Scale bar = 100 nm.

 Figure 18 shows the clearance of 3 H-DNA and 14 C-lipid from particles
25 (prepared by reverse-phase methods) after injection into ICR mice. The figure includes free 3 H-DNA after injection as a comparison. Lipid composition is POPC:DODAC:PEG-Cer- C_{20} .

 Figures 19A and 19B show the clearance 3 H-DNA and 14 C-lipid from
 particles (prepared by detergent dialysis methods) after injection into ICR mice. Lipid
30 compositions were (A) DOPE:DODAC-PEG-Cer- C_{20} (84:6:10) and (B)
 DOPE:DODAC-PEG-Cer- C_{14} (84:6:10).

 Figure 20 shows the results of *in vivo* gene transfer which occurs in the
 lungs of mice. Lipid composition is DOPE-DODAC-PEG-Cer- C_{20} or
 DOPE:DODAC-PEG-Cer- C_{14} (84:6:10).

Figure 21 shows the results of *in vivo* gene transfer which occurs in the liver mice. Lipid composition is DOPE-DODAC-PEG-Cer-C₂₀ or DOPE:DODAC:PEG-Cer-C₁₄ (84:6:10).

Figure 22 shows the results of *in vivo* gene transfer which occurs in the spleen of mice. Lipid composition is DOPE-DODAC-PEG-Cer-C₂₀ or DOPE:DODAC:PEG-Cer-C₁₄ (84:6:10).

Figure 23 shows the effect of increasing amounts of LIPOFECTIN® (DOTMA/DOPE; 50:50 mol ratio) on the recovery of β gal plasmid DNA in the aqueous phase following Bligh and Dyer extraction of the lipid-nucleic acid complexes.

Figures 24A and 24B show the effect of increasing amounts of cationic lipid on the recovery of plasmid DNA in the aqueous (A) and organic (B) phase following Bligh and Dyer extraction of the lipid-nucleic acid complexes.

Figures 25A, 25B, 25C and 25D show the recovery of plasmid DNA from aqueous (A and C) and organic (B and D) fractions following Bligh and Dyer extraction and expressed as a function of charge ratio (+/-).

Figures 26A and 26B illustrate the DNA condensation by poly-L-lysine and DODAC assayed by TO-PRO-1 dye intercalation. Condensation state was assessed in a Bligh and Dyer monophasic (A) and in 100 mM OGP (B).

Figure 27 illustrates the effects of increasing amounts of OGP on the recovery of plasmid DNA from the aqueous and organic phases following Bligh and Dyer extraction of lipid-nucleic acid complexes (plasmid/DODAC).

Figure 28 shows the effects of increasing amounts of NaCl on the recovery of plasmid DNA from the aqueous phase following Bligh and Dyer extraction of lipid-nucleic acid complexes.

Figures 29A and 29B show the effect of poly-L-lysine and DODAC on the electrophoretic mobility of plasmid DNA.

Figure 30 illustrates a protocol for preparing lipid-nucleic acid particles using detergent dialysis.

Figures 31A and B are bar graphs which illustrates the QELS results of a typical lipid-nucleic acid complex mixture prepared from β -gal plasmid/DODAC/ESM.

Figure 32 is a bar graph which illustrates the fluorescence spectroscopic evaluation of DNA condensation in the lipid-nucleic acid complexes using TO-PRO-1 dye intercalation. The results show that β -gal plasmid in DODAC/ESM is condensed and protected against dye intercalation by the lipid, and that OGP can uncondense the

particle.

Figure 33 shows the results of electrophoresis of DNA extracted from lipid-nucleic acid complexes following digestion with DNase I. DNA within the complex is protected from DNase I degradation whereas uncomplexed DNA is not protected.

Figure 34 provides the results of CHO cell lipofection using β -gal plasmid/DODAC/ESM as assayed by β -gal enzyme activity.

Figures 35A and B show changes in sample turbidity measured by 90° light scattering at 600 nm during the preparation of nucleic acid-lipid particles in the presence of 100 mM (A) or 20 mM (B) *n*-octyl β -D-glucopyranoside (OGP).

Figure 36 shows solubilization of preformed DODAC (●) and SM (■) vesicles in OGP as measured by 90° light scattering. The concentrations of lipids used were 200 μ M (solid lines) and 800 μ M (broken lines).

Figures 37A, 37B and 37C show volume-weighting particle size distribution determined by QELS operating in solid particle analysis mode for a nucleic acid-lipid particle formulation composed of pCMV β /DODAC/SM (charge ratio of 2:1, DODAC/SM mole ratio of 1:1) and prepared using 20 mM OGP before (●) and after (■) dialysis (A). The same nucleic acid-lipid particle formulation after dialysis was also examined by electron microscopy (B, negative stain and C, freeze-fracture). Bar = 100 nm.

Figures 38A and 37B depict the agarose gel electrophoresis of DNA isolated from formulations prepared in 100 mM and 20 mM OGP (charge ratio of 2:1 and SM/DODAC ratio of 1:1) and tested for DNase I sensitivity in the absence (A) and presence (B) of OGP. Panel A: molecular weight standards (lane 1), pCMV β in the absence of added lipid or DNase I (lane 2), pCMV β following incubation with DNase I (lane 3), DNA isolated from a dialyzed nucleic acid-lipid particle formulation prepared using 100 mM OGP following incubations in the absence (lane 4) and presence (lane 5) of DNase I, and DNA isolated from particles prepared using 20 mM OGP and dialyzed following incubations in the absence (lane 6) and presence (lane 7) of DNase I. The first 3 lanes in panel B are identical to those in panel A except that pCMV β was incubated in 20 mM OGP in the absence (lane 2) and presence (lane 3) of DNase I. DNA isolated from a formulation prepared in 20 mM OGP (prior to detergent removal) was incubated in the absence (lane 4) and presence (lane 5) of DNase I in 20 mM OGP. Arrow indicates degraded DNA.

Figures 39A, 39B and 39C show *in vitro* Chinese Hamster Ovary (CHO)

cell lipofection using nucleic acid-lipid particle formulations composed of pCMV β /SM/DODAC (SM/DODAC mole ratio of 1:1 and charge ratio of 1:1 to 8:1) prepared using 100 mM OGP followed by dialysis. (A) Influence of charge ratio on β -galactosidase lipofection. (B) Particle induced toxicity as measured by reduced β -galactosidase activity per well for formulations prepared using a charge ratio of 4:1. (C) β -galactosidase lipofection achieved with nucleic acid-lipid particles prepared using SM (solid bar) or DOPE (hatched bar) as the neutral lipid (charge ratio of 4:1 and DODAC to neutral lipid mole ratio of 1:1).

Figure 40 is a model describing the intermediates that may be involved in the generation of a novel lipid-DNA particle.

Figures 41A, 41B and 41C illustrate the encapsulation of plasmid DNA in a lipid vesicles by the detergent dialysis method using different cationic lipids.

Figures 42A, 42B and 42C demonstrate the stability of plasmid containing vesicles prepared with different cationic lipids.

Figure 43 demonstrates the encapsulation of plasmid DNA with the ionizable lipid AL-1 ($pK_a = 6.6$) by the dialysis method

Figures 44 and 45 show the stability of the plasmid containing vesicles formed with AL-1 at pH 4.8 and the protection of the entrapped DNA from degradation by serum nucleases at pH 7.5.

Figure 46 demonstrates the effect of the PEG-ceramide concentration on the encapsulation efficiency by the dialysis method with 7.5 % DODAC and DOPE.

DETAILED DESCRIPTION OF THE INVENTION

CONTENTS

	I.	Glossary
	II.	General
5	III.	Embodiments of the invention
	A.	Lipid-Nucleic Acid Particles, and Properties Thereof
	B.	Methods of Formulating Lipid-Nucleic Acid Particles
	C.	Pharmaceutical Preparations
10	D.	Administration of Lipid-Nucleic Acid Particle Formulations for Gene Transfer
	IV.	Examples
	V.	Conclusion

I. Glossary

The following abbreviations are used herein: CHO, Chinese hamster ovary cell line; B16, murine melanoma cell line; DC-Chol, 3 β -(N-(N',N'-dimethylaminoethane)carbamoyl) cholesterol (see, Gao, *et al.*, Biochem. Biophys. Res. Comm. 179:280-285 (1991)); DDAB, N,N-distearyl-N,N-dimethylammonium bromide; DMRIE, N-(1,2-dimyristyloxyprop-3-yl)-N,N-dimethyl-N-hydroxyethyl ammonium bromide; DODAC, N,N-dioleoyl-N,N-dimethylammonium chloride; DOGS, diheptadecylamidoglycyl spermidine; DOPE, 1,2-*sn*-dioleoylphosphatidylethanolamine; DOSPA, N-(1-(2,3-dioleoyloxy)propyl)-N-(2-(sperminocarboxamido)ethyl)-N,N-dimethylammonium trifluoroacetate; DOTAP, N-(1-(2,3-dioleoyloxy)propyl)-N,N,N-trimethylammonium chloride; DOTMA, N-(1-(2,3-dioleoyloxy)propyl)-N,N,N-trimethylammonium chloride; EPC, egg phosphatidylcholine; ESM, egg sphingomyelin; RT, room temperature; TBE, Tris-Borate-EDTA (89 mM in Tris-borate and 2 mM in EDTA); HEPES, 4-(2-hydroxyethyl)-1-piperazineethanesulfonic acid; HBS, HEPES buffered saline (150 mM NaCl and 20 mM HEPES); PEG-Cer-C₂₀, 1-O-(2'-(ω -methoxypolyethyleneglycol)succinoyl)-2-N-arachidoyl-sphingosine; PEG-Cer-C₁₄, 1-O-(2'-(ω -

-methoxypolyethyleneglycol)succinoyl)-2-N-myristoyl-sphingosine; PBS, phosphate-buffered saline; EGTA, ethylenebis(oxyethylenenitrilo)-tetraacetic acid; OGP, n-octyl β -D-glycopyranoside (Sigma Chemical Co., St. Louis, MO); POPC, palmitoyl oleoyl phosphatidylcholine (Northern Lipids, Vancouver, BC); QELS, quasielastic light scattering; TBE, 89 mM Tris-borate with 2 mM EDTA; and EDTA, Ethylenediaminetetraacetic acid (Fisher Scientific, Fair Lawn, NJ).

The term "acyl" refers to a radical produced from an organic acid by removal of the hydroxyl group. Examples of acyl radicals include acetyl, pentanoyl, palmitoyl, stearoyl, myristoyl, caproyl and oleoyl.

As used herein, the term "pharmaceutically acceptable anion" refers to anions of organic and inorganic acids which provide non-toxic salts in pharmaceutical preparations. Examples of such anions include chloride, bromide, sulfate, phosphate, acetate, benzoate, citrate, glutamate, and lactate. The preparation of pharmaceutically acceptable salts is described in Berge, *et al.*, J. Pharm. Sci. 66:1-19 (1977), incorporated herein by reference.

The term "lipid" refers to any fatty acid derivative which is capable of forming a bilayer such that a hydrophobic portion of the lipid material orients toward the bilayer while a hydrophilic portion orients toward the aqueous phase. Amphipathic lipids are necessary as the primary lipid vesicle structural element. Hydrophilic characteristics derive from the presence of phosphato, carboxylic, sulfato, amino, sulfhydryl, nitro, and other like groups. Hydrophobicity could be conferred by the inclusion of groups that include, but are not limited to, long chain saturated and unsaturated aliphatic hydrocarbon groups and such groups substituted by one or more aromatic, cycloaliphatic or heterocyclic group(s). Preferred lipids are phosphoglycerides and sphingolipids, representative examples of which include phosphatidylcholine, phosphatidylethanolamine, phosphatidylserine, phosphatidylinositol, phosphatidic acid, palmitoyl oleoyl phosphatidylcholine, lysophosphatidylcholine, lysophosphatidylethanolamine, dipalmitoylphosphatidylcholine, dioleoylphosphatidylcholine, distearoylphosphatidylcholine or dilinoleoylphosphatidylcholine could be used. Other compounds lacking in phosphorus, such as sphingolipid and glycosphingolipid families are also within the group designated as lipid. Additionally, the amphipathic lipids described above may be mixed with other lipids including triglycerides and sterols.

The term "neutral" refers to any of a number of lipid species which exist

either in an uncharged form, a neutral zwitterionic form. Such lipids include, for example diacylphosphatidylcholine, diacylphosphatidylethanolamine, ceramide, sphingomyelin, cephalin, and cerebroside.

The term "non-cationic lipid" refers to any neutral lipid as described above as well as anionic lipids. Examples of anionic lipids include cardiolipin, diacylphosphatidylserine and diacylphosphatidic acid.

The term "cationic lipid" refers to any of a number of lipid species which carry a net positive charge at physiological pH. Such lipids include, but are not limited to, DODAC, DOTMA, DDAB, DOTAP, DC-Chol and DMRIE. Additionally, a number of commercial preparations of cationic lipids are available which can be used in the present invention. These include, for example, LIPOFECTIN® (commercially available cationic liposomes comprising DOTMA and DOPE, from GIBCO/BRL, Grand Island, New York, USA); LIPOFECTAMINE® (commercially available cationic liposomes comprising DOSPA and DOPE, from GIBCO/BRL); and TRANSFECTAM® (commercially available cationic lipids comprising DOGS from Promega Corp., Madison, Wisconsin, USA).

The term "nucleic acid" refers to a deoxyribonucleotide or ribonucleotide polymer in either single- or double-stranded form. Unless otherwise specified, the term nucleic acid is used interchangeably with gene, DNA, cDNA, RNA, and mRNA. The term specifically encompasses ribozymes; nucleic acid cloning and/or expression vectors such as plasmids; genetically engineered viral genomes, expression cassettes, and chromosomes from mammalian (especially human) sources.

The terms "gene transfer", "transfection", and "transformation" are used herein interchangeably, and refer to the introduction of polyanionic materials, particularly nucleic acids, into cells. The term "lipofection" refers to the introduction of such materials using lipid-based complexes. The polyanionic materials can be in the form of DNA or RNA which is linked to expression vectors to facilitate gene expression after entry into the cell. Thus the polyanionic material used in the present invention is meant to include DNA having coding sequences for structural proteins, receptors and hormones, as well as transcriptional and translational regulatory elements (*i.e.*, promoters, enhancers, terminators and signal sequences) and vectors. Methods of incorporating particular nucleic acids into expression vectors are well known to those of skill in the art, but are described in detail in, for example, Sambrook *et al.*, *Molecular Cloning: A Laboratory Manual* (2nd ed.), Vols. 1-3, Cold Spring Harbor Laboratory, (1989) or

Current Protocols in Molecular Biology, F. Ausubel *et al.*, ed. Greene Publishing and Wiley-Interscience, New York (1987), both of which are incorporated herein by reference.

"Expression vectors", "cloning vectors", or "vectors" are nucleic acid molecules (such as plasmids) that are able to replicate in a chosen host cell. Expression vectors may replicate autonomously, or they may replicate by being inserted into the genome of the host cell, by methods well known in the art. Vectors that replicate autonomously will have an origin of replication or autonomous replicating sequence (ARS) that is functional in the chosen host cell(s). Often, it is desirable for a vector to be usable in more than one host cell, *e.g.*, in *E. coli* for cloning and construction, and in a mammalian cell for expression.

The term "hydrophobic" as applied to DNA and DNA complexes, refers to complexes which are substantially more soluble in organic solvents than in aqueous solutions. More particularly, hydrophobic DNA and DNA complexes are those which are at least 50% soluble in organic solvents such as chloroform/methanol mixtures, and preferably more than 70% soluble, more preferably more than 90% soluble in such organic solvents.

II. General

Gene transfer techniques that involve the use of liposomes have been described previously in the art (U.S. Patents 5,049,386; 4,946,787; and 4,897,355). General lipofection protocols are also described in the following references: Behr *et al.* (1989) Proc. Natl. Acad. Sci. (U.S.A.) **86**: 6982; Demeneix *et al.* (1991) Int. J. Dev. Biol. **35**: 481; Loeffler *et al.* (1990) J. Neurochem. **54**: 1812; Bennett *et al.* (1992) Mol. Pharmacol. **41**: 1023; Bertling *et al.* (1991) Biotechnol. Appl. Biochem. **13**: 390; Felgner *et al.* (1987) Proc. Natl. Acad. Sci. (U.S.A.) **84**: 7413; Felgner and Ringold (1989) Nature **337**: 387; Gareis *et al.* (1991) Cell. Mol. Biol. **37**: 191; Jarnagin *et al.* (1992) Nucleic Acids Res. **20**: 4205; Jiao *et al.* (1992) Exp. Neurol. **115**: 400; Lim *et al.* (1991) Circulation **83**: 2007; Malone *et al.* (1989) Proc. Natl. Acad. Sci. (U.S.A.) **86**: 6077; Powell *et al.* (1992) Eur. J. Vasc. Surg. **6**: 130; Strauss and Jaenisch (1992) EMBO J. **11**: 417; and Leventis and Silvius (1990) Biochim. Biophys. Acta **1023**: 124. Lipofection reagents are sold commercially (*e.g.*, "Transfectam" and "Lipofectin"). Cationic and neutral lipids that are reportedly suitable for efficient lipofection of nucleic acids include those of Felgner (WO91/17424; WO91/16024). In addition, a combination

of neutral and cationic lipid has been shown to be highly efficient at lipofection of animal cells and showed a broad spectrum of effectiveness in a variety of cell lines (Rose *et al.* (1991) BioTechniques 10: 520. The above lipofection protocols may be adapted for use in the present invention, and the preceding references are therefore incorporated in their entirety.

III. Embodiments of the invention

A. Lipid-Nucleic Acid Particles, and Properties Thereof

In one aspect, the present invention provides novel, lipid-nucleic acid complexes consisting essentially of cationic lipids and nucleic acids.

1. Lipid Components

Various suitable cationic lipids may be used in the present invention, either alone or in combination with one or more other cationic lipid species or neutral lipid species.

Cationic lipids which are useful in the present invention can be any of a number of lipid species which carry a net positive charge at physiological pH, for example: DODAC, DOTMA, DDAB, DOTAP, DOSPA, DOGS, DC-Chol and DMRIE, or combinations thereof. A number of these lipids and related analogs, which are also useful in the present invention, have been described in co-pending USSN 08/316,399; U.S. Patent Nos. 5,208,036, 5,264,618, 5,279,833 and 5,283,185, the disclosures of which are incorporated herein by reference. Additionally, a number of commercial preparations of cationic lipids are available and can be used in the present invention. These include, for example, LIPOFECTIN® (commercially available cationic liposomes comprising DOTMA and DOPE, from GIBCO/BRL, Grand Island, New York, USA); LIPOFECTAMINE® (commercially available cationic liposomes comprising DOSPA and DOPE, from GIBCO/BRL); and TRANSFECTAM® (commercially available cationic liposomes comprising DOGS from Promega Corp., Madison, Wisconsin, USA).

The non-cationic lipids used in the present invention can be any of a variety of neutral uncharged, zwitterionic or anionic lipids capable of producing a stable complex. They are preferably neutral, although they can alternatively be positively or negatively charged. Examples of non-cationic lipids useful in the present invention include: phospholipid-related materials, such as lecithin, phosphatidylethanolamine,

lysolecithin, lysophosphatidylethanolamine, phosphatidylserine, phosphatidylinositol, sphingomyelin, cephalin, cardiolipin, phosphatidic acid, cerebroside, dicetylphosphate, dioleoylphosphatidylcholine (DOPC), dipalmitoyl-phosphatidylcholine (DPPC), diolenylphosphatidylglycerol (DOPG), dipalmitoylphosphatidylglycerol (DPPG), dioleoyl-phosphatidylethanolamine (DOPE), palmitoyloleoyl-phosphatidylcholine (POPC), palmitoyloleoyl-phosphatidylethanolamine (POPE) and dioleoyl-phosphatidylethanolamine 4-(N-maleimidomethyl)-cyclohexane-1-carboxylate (DOPE-mal). Additional non-phosphorous containing lipids are, *e.g.*, stearylamine, dodecylamine, hexadecylamine, acetyl palmitate, glycerolricinoleate, hexadecyl stearate, isopropyl myristate, amphoteric acrylic polymers, triethanolamine-lauryl sulfate, alkyl-aryl sulfate polyethyloxylated fatty acid amides, dioctadecyldimethyl ammonium bromide and the like, diacylphosphatidylcholine, diacylphosphatidylethanolamine, ceramide, sphingomyelin, cephalin, and cerebroside. Other lipids such as lysophosphatidylcholine and lysophosphatidylethanolamine may be present. Non-cationic lipids also include polyethylene glycol-based polymers such as PEG 2000, PEG 5000 and polyethylene glycol conjugated to phospholipids or to ceramides (referred to as PEG-Cer), as described in co-pending USSN 08/316,429, incorporated herein by reference.

In preferred embodiments, the non-cationic lipids are diacylphosphatidylcholine (*e.g.*, dioleoylphosphatidylcholine, dipalmitoylphosphatidylcholine and dilinoleoylphosphatidylcholine), diacylphosphatidylethanolamine (*e.g.*, dioleoylphosphatidylethanolamine and palmitoyloleoylphosphatidylethanolamine), ceramide or sphingomyelin. The acyl groups in these lipids are preferably acyl groups derived from fatty acids having C₁₀-C₂₄ carbon chains. More preferably the acyl groups are lauroyl, myristoyl, palmitoyl, stearoyl or oleoyl. In particularly preferred embodiments, the non-cationic lipid will be 1,2-*sn*-dioleoylphosphatidylethanolamine, or egg sphingomyelin (ESM).

2. Nucleic acid components

While the invention is described in the examples with reference to the use of plasmids, one of skill in the art will understand that the methods described herein are equally applicable to other larger nucleic acids or oligonucleotides.

The nucleic acids which are useful in the present invention (including both the complexes and particles) are typically nucleotide polymers having from 10 to 100,000 nucleotide residues. Typically, the nucleic acids are to be administered to a subject for the purpose of repairing or enhancing the expression of a cellular protein. Additionally,

the nucleic acid can carry a label (*e.g.*, radioactive label, fluorescent label or colorimetric label) for the purpose of providing clinical diagnosis relating to the presence or absence of complementary nucleic acids. Accordingly, the nucleic acids, or nucleotide polymers, can be polymers of nucleic acids including genomic DNA, cDNA, mRNA or oligonucleotides containing nucleic acid analogs, for example, the antisense derivatives described in a review by Stein, *et al.*, *Science* **261**:1004-1011 (1993) and in U.S. Patent Nos. 5,264,423 and 5,276,019, the disclosures of which are incorporated herein by reference. Still further, the nucleic acids may encode transcriptional and translational regulatory sequences including promoter sequences and enhancer sequences.

The nucleotide polymers can be single-stranded DNA or RNA, or double-stranded DNA or DNA-RNA hybrids. Examples of double-stranded DNA include structural genes, genes including control and termination regions, and self-replicating systems such as plasmid DNA.

Single-stranded nucleic acids include antisense oligonucleotides (complementary to DNA and RNA), ribozymes and triplex-forming oligonucleotides. In order to increase stability, some single-stranded nucleic acids will preferably have some or all of the nucleotide linkages substituted with stable, non-phosphodiester linkages, including, for example, phosphorothioate, phosphorodithioate, phosphoroselenate, or O-alkyl phosphotriester linkages.

The nucleic acids used in the present invention will also include those nucleic acids in which modifications have been made in one or more sugar moieties and/or in one or more of the pyrimidine or purine bases. Examples of sugar modifications include replacement of one or more hydroxyl groups with halogens, alkyl groups, amines, azido groups or functionalized as ethers or esters. Additionally, the entire sugar may be replaced with sterically and electronically similar structures, including aza-sugars and carbocyclic sugar analogs. Modifications in the purine or pyrimidine base moiety include, for example, alkylated purines and pyrimidines, acylated purines or pyrimidines, or other heterocyclic substitutes known to those of skill in the art.

Multiple genetic sequences can be also be used in the present methods. Thus, the sequences for different proteins may be located on one strand or plasmid. Non-encoding sequences may be also be present, to the extent that they are necessary to achieve appropriate expression.

The nucleic acids used in the present method can be isolated from natural

sources, obtained from such sources as ATCC or GenBank libraries or prepared by synthetic methods. Synthetic nucleic acids can be prepared by a variety of solution or solid phase methods. Generally, solid phase synthesis is preferred. Detailed descriptions of the procedures for solid phase synthesis of nucleic acids by phosphite-triester, phosphotriester, and H-phosphonate chemistries are widely available. See, for example, Itakura, U.S. Pat. No. 4,401,796; Caruthers, *et al.*, U.S. Pat. Nos. 4,458,066 and 4,500,707; Beaucage, *et al.*, Tetrahedron Lett., **22**:1859-1862 (1981); Matteucci, *et al.*, J. Am. Chem. Soc., **103**:3185-3191 (1981); Caruthers, *et al.*, Genetic Engineering, **4**:1-17 (1982); Jones, chapter 2, Atkinson, *et al.*, chapter 3, and Sproat, *et al.*, chapter 4, in *Oligonucleotide Synthesis: A Practical Approach*, Gait (ed.), IRL Press, Washington D.C. (1984); Froehler, *et al.*, Tetrahedron Lett., **27**:469-472 (1986); Froehler, *et al.*, Nucleic Acids Res., **14**:5399-5407 (1986); Sinha, *et al.* Tetrahedron Lett., **24**:5843-5846 (1983); and Sinha, *et al.*, Nucl. Acids Res., **12**:4539-4557 (1984) which are incorporated herein by reference.

a. **Vectors for introduction and expression of genes in cells**

An important aspect of this invention is the use of the lipid-nucleic acid particles provided herein to introduce selected genes into cells *in vitro* and *in vivo*, followed by expression of the selected gene in the host cell. Thus, the nucleic acids in the particles specifically encompass vectors that are capable of being expressed in a host cell. Promoter, enhancer, stress or chemically-regulated promoters, antibiotic-sensitive or nutrient-sensitive regions, as well as therapeutic protein encoding sequences, may be included as required.

In brief summary, the expression of natural or synthetic nucleic acids is typically achieved by operably linking a nucleic acid of interest to a promoter (which is either constitutive or inducible), incorporating the construct into an expression vector, and introducing the vector into a suitable host cell. Typical vectors contain transcription and translation terminators, transcription and translation initiation sequences, and promoters useful for regulation of the expression of the particular nucleic acid. The vectors optionally comprise generic expression cassettes containing at least one independent terminator sequence, sequences permitting replication of the cassette in eukaryotes, or prokaryotes, or both, (*e.g.*, shuttle vectors) and selection markers for both prokaryotic and eukaryotic systems. Vectors are suitable for replication and integration in prokaryotes, eukaryotes, or preferably both. See, Gilman and Smith (1979), *Gene*, **8**:

81-97; Roberts *et al.* (1987), *Nature*, 328: 731-734; Berger and Kimmel, *Guide to Molecular Cloning Techniques, Methods in Enzymology*, volume 152, Academic Press, Inc., San Diego, CA (Berger); Sambrook *et al.* (1989), *MOLECULAR CLONING - A LABORATORY MANUAL* (2nd ed.) Vol. 1-3, Cold Spring Harbor Laboratory, Cold Spring Harbor Press, N.Y., (Sambrook); and F.M. Ausubel *et al.*, *CURRENT PROTOCOLS IN MOLECULAR BIOLOGY*, eds., Current Protocols, a joint venture between Greene Publishing Associates, Inc. and John Wiley & Sons, Inc., (1994 Supplement) (Ausubel). Product information from manufacturers of biological reagents and experimental equipment also provide information useful in known biological methods. Such manufacturers include the SIGMA chemical company (Saint Louis, MO), R&D systems (Minneapolis, MN), Pharmacia LKB Biotechnology (Piscataway, NJ), CLONTECH Laboratories, Inc. (Palo Alto, CA), Chem Genes Corp., Aldrich Chemical Company (Milwaukee, WI), Glen Research, Inc., GIBCO BRL Life Technologies, Inc. (Gaithersburg, MD), Fluka Chemica-Biochemika Analytika (Fluka Chemie AG, Buchs, Switzerland), and Applied Biosystems (Foster City, CA), as well as many other commercial sources known to one of skill.

Vectors to which foreign nucleic acids are operably linked may be used to introduce these nucleic acids into host cells and mediate their replication and/or expression. "Cloning vectors" are useful for replicating and amplifying the foreign nucleic acids and obtaining clones of specific foreign nucleic acid-containing vectors. "Expression vectors" mediate the expression of the foreign nucleic acid. Some vectors are both cloning and expression vectors.

In general, the particular vector used to transport a foreign gene into the cell is not particularly critical. Any of the conventional vectors used for expression in the chosen host cell may be used.

An expression vector typically comprises a eukaryotic transcription unit or "expression cassette" that contains all the elements required for the expression of exogenous genes in eukaryotic cells. A typical expression cassette contains a promoter operably linked to the DNA sequence encoding a desired protein and signals required for efficient polyadenylation of the transcript.

Eukaryotic promoters typically contain two types of recognition sequences, the TATA box and upstream promoter elements. The TATA box, located 25-30 base pairs upstream of the transcription initiation site, is thought to be involved in directing RNA polymerase to begin RNA synthesis. The other upstream promoter elements

determine the rate at which transcription is initiated.

Enhancer elements can stimulate transcription up to 1,000 fold from linked homologous or heterologous promoters. Enhancers are active when placed downstream or upstream from the transcription initiation site. Many enhancer elements derived from viruses have a broad host range and are active in a variety of tissues. For example, the SV40 early gene enhancer is suitable for many cell types. Other enhancer/promoter combinations that are suitable for the present invention include those derived from polyoma virus, human or murine cytomegalovirus, the long term repeat from various retroviruses such as murine leukemia virus, murine or Rous sarcoma virus and HIV. See, *Enhancers and Eukaryotic Expression*, Cold Spring Harbor Press, Cold Spring Harbor, N.Y. 1983, which is incorporated herein by reference.

In addition to a promoter sequence, the expression cassette should also contain a transcription termination region downstream of the structural gene to provide for efficient termination. The termination region may be obtained from the same source as the promoter sequence or may be obtained from a different source.

If the mRNA encoded by the selected structural gene is to be efficiently translated, polyadenylation sequences are also commonly added to the vector construct. Two distinct sequence elements are required for accurate and efficient polyadenylation: GU or U rich sequences located downstream from the polyadenylation site and a highly conserved sequence of six nucleotides, AAUAAA, located 11-30 nucleotides upstream. Termination and polyadenylation signals that are suitable for the present invention include those derived from SV40, or a partial genomic copy of a gene already resident on the expression vector.

In addition to the elements already described, the expression vector of the present invention may typically contain other specialized elements intended to increase the level of expression of cloned nucleic acids or to facilitate the identification of cells that carry the transduced DNA. For instance, a number of animal viruses contain DNA sequences that promote the extra chromosomal replication of the viral genome in permissive cell types. Plasmids bearing these viral replicons are replicated episomally as long as the appropriate factors are provided by genes either carried on the plasmid or with the genome of the host cell.

The expression vectors of the present invention will typically contain both prokaryotic sequences that facilitate the cloning of the vector in bacteria as well as one or more eukaryotic transcription units that are expressed only in eukaryotic cells, such as

mammalian cells. The prokaryotic sequences are preferably chosen such that they do not interfere with the replication of the DNA in eukaryotic cells.

Selected genes are normally be expressed when the DNA sequence is functionally inserted into a vector. "Functionally inserted" means that it is inserted in proper reading frame and orientation and operably linked to proper regulatory elements. Typically, a gene will be inserted downstream from a promoter and will be followed by a stop codon, although production as a hybrid protein followed by cleavage may be used, if desired.

Expression vectors containing regulatory elements from eukaryotic viruses such as retroviruses are typically used. SV40 vectors include pSVT7 and pMT2. Vectors derived from bovine papilloma virus include pBV-1MTHA, and vectors derived from Epstein Bar virus include pHEBO, and p205. Other exemplary vectors include pMSG, pAV009/A⁺, pMTO10/A⁺, pMAMneo-5, baculovirus pDSVE, and any other vector allowing expression of proteins under the direction of the SV-40 early promoter, SV-40 later promoter, metallothionein promoter, murine mammary tumor virus promoter, Rous sarcoma virus promoter, polyhedrin promoter, or other promoters shown effective for expression in eukaryotic cells.

While a variety of vectors may be used, it should be noted that viral vectors such as retroviral vectors are useful for modifying eukaryotic cells because of the high efficiency with which the retroviral vectors transfect target cells and integrate into the target cell genome. Additionally, the retroviruses harboring the retroviral vector are capable of infecting cells from a wide variety of tissues.

In addition to the retroviral vectors mentioned above, cells may be lipofected with adeno-associated viral vectors. See, *e.g.*, *Methods in Enzymology*, Vol. 185, Academic Press, Inc., San Diego, CA (D.V. Goeddel, ed.) (1990) or M. Krieger (1990), *Gene Transfer and Expression -- A Laboratory Manual*, Stockton Press, New York, NY, and the references cited therein. Adeno associated viruses (AAVs) require helper viruses such as adenovirus or herpes virus to achieve productive infection. In the absence of helper virus functions, AAV integrates (site-specifically) into a host cell's genome, but the integrated AAV genome has no pathogenic effect. The integration step allows the AAV genome to remain genetically intact until the host is exposed to the appropriate environmental conditions (*e.g.*, a lytic helper virus), whereupon it re-enters the lytic life-cycle. Samulski (1993), *Current Opinion in Genetic and Development*, 3: 74-80, and the references cited therein provides an overview of the AAV life cycle. See

also West *et al.* (1987), *Virology*, 160: 38-47; Carter *et al.* (1989), U.S. Patent No. 4,797,368; Carter *et al.* (1993), WO 93/24641; Kotin (1994), *Human Gene Therapy*, 5: 793-801; Muzyczka (1994), *J. Clin. Invest.*, 94: 1351 and Samulski, *supra*, for an overview of AAV vectors.

5 Plasmids designed for producing recombinant vaccinia, such as pGS62, (Langford, C. L. *et al.* (1986), *Mol. Cell. Biol.*, 6: 3191-3199) may also be used. This plasmid consists of a cloning site for insertion of foreign nucleic acids, the P7.5 promoter of vaccinia to direct synthesis of the inserted nucleic acid, and the vaccinia TK gene flanking both ends of the foreign nucleic acid.

10 Whatever the vector is used, generally the vector is genetically engineered to contain, in expressible form, a gene of interest. The particular gene selected will depend on the intended treatment. Examples of such genes of interest are described below at Section D.3. Insertion of Functional Copy of a Gene, and throughout the specification.

15 The vectors further usually comprise selectable markers which result in nucleic acid amplification such as the sodium, potassium ATPase, thymidine kinase, aminoglycoside phosphotransferase, hygromycin B phosphotransferase, xanthine-guanine phosphoribosyl transferase, CAD (carbamyl phosphate synthetase, aspartate transcarbamylase, and dihydroorotase), adenosine deaminase, dihydrofolate reductase, 20 and asparagine synthetase and ouabain selection. Alternatively, high yield expression systems not involving nucleic acid amplification are also suitable, such as using a baculovirus vector in insect cells, with the encoding sequence under the direction of the polyhedrin promoter or other strong baculovirus promoters.

25 When nucleic acids other than plasmids are used the nucleic acids can contain nucleic acid analogs, for example, the antisense derivatives described in a review by Stein, *et al.*, *Science* 261:1004-1011 (1993) and in U.S. Patent Nos. 5,264,423 and 5,276,019, the disclosures of which are incorporated herein by reference.

B. Methods of making the particles

30 In one embodiment, the present invention provides lipid-nucleic acid particles produced via novel, hydrophobic nucleic acid-lipid intermediate complexes. The complexes are preferably charge-neutralized. Manipulation of these complexes in either detergent-based or organic solvent-based systems can lead to particle formation in which the nucleic acid is protected.

Lipid-nucleic acid formulations can be formed by combining the nucleic acid with a preformed cationic liposome (see, U.S. Patent Nos. 4,897,355, 5,264,618, 5,279,833 and 5,283,185). In such methods, the nucleic acid is attracted to the cationic surface charge of the liposome and the resulting complexes are thought to be of the liposome-covered "sandwich-type." As a result, a portion of the nucleic acid or plasmid remains exposed in serum and can be degraded by enzymes such as DNase I. Others have attempted to incorporate the nucleic acid or plasmid into the interior of a liposome during formation. These methods typically result in the aggregation in solution of the cationic lipid-nucleic acid complexes (see Figure 2). Passive loading of a plasmid into a preformed liposome has also not proven successful. Finally, the liposome-plasmid complexes which have been formed are typically 200 to 400 nm in size and are therefore cleared more rapidly from circulation than smaller sized complexes or particles.

The present invention provides a method of preparing serum-stable plasmid-lipid particles in which the plasmid is encapsulated in a lipid-bilayer and is protected from degradation. Additionally, the particles formed in the present invention are preferably neutral or negatively-charged at physiological pH. For *in vivo* applications, neutral particles are advantageous, while for *in vitro* applications the particles are more preferably negatively charged. This provides the further advantage of reduced aggregation over the positively-charged liposome formulations in which a nucleic acid can be encapsulated in cationic lipids.

The particles made by the methods of this invention have a size of about 50 to about 150 nm, with a majority of the particles being about 65 to 85 nm. The particles can be formed by either a detergent dialysis method or by a modification of a reverse-phase method which utilizes organic solvents to provide a single phase during mixing of the components. Without intending to be bound by any particular mechanism of formation, Figure 3 depicts a detergent dialysis approach to the formation of the plasmid-lipid particles. With reference to Figure 3, a plasmid or other large nucleic acid is contacted with a detergent solution of cationic lipids to form a coated plasmid complex. These coated plasmids can aggregate and precipitate. However, the presence of a detergent reduces this aggregation and allows the coated plasmids to react with excess lipids (typically, non-cationic lipids) to form particles in which the plasmid is encapsulated in a lipid bilayer. As noted above, these particles differ from the more classical liposomes both in size (liposomes being typically 200-400 nm) in that there is little or no aqueous medium encapsulated by the particle's lipid bilayer. The methods

described below for the formation of plasmid-lipid particles using organic solvents follow a similar scheme.

In some embodiments, the particles are formed using detergent dialysis. Thus, the present invention provides a method for the preparation of serum-stable plasmid-lipid particles, comprising:

- (a) combining a plasmid with cationic lipids in a detergent solution to form a coated plasmid-lipid complex;
- (b) contacting non-cationic lipids with the coated plasmid-lipid complex to form a detergent solution comprising a plasmid-lipid complex and non-cationic lipids; and
- (c) dialyzing the detergent solution of step (b) to provide a solution of serum-stable plasmid-lipid particles, wherein the plasmid is encapsulated in a lipid bilayer and the particles are serum-stable and have a size of from about 50 to about 150 nm.

An initial solution of coated plasmid-lipid complexes is formed by combining the plasmid with the cationic lipids in a detergent solution.

In these embodiments, the detergent solution is preferably an aqueous solution of a neutral detergent having a critical micelle concentration of 15-300 mM, more preferably 20-50 mM. Examples of suitable detergents include, for example, N,N'-((octanoylimino)-bis-(trimethylene))-bis-(D-gluconamide) (BIGCHAP); BRIJ 35; Deoxy-BIGCHAP; dodecylpoly(ethylene glycol) ether; Tween 20; Tween 40; Tween 60; Tween 80; Tween 85; Mega 8; Mega 9; Zwittergent[®] 3-08; Zwittergent[®] 3-10; Triton X-405; hexyl-, heptyl-, octyl- and nonyl- β -D-glucopyranoside; and heptylthioglucopyranoside; with octyl β -D-glucopyranoside and Tween-20 being the most preferred. The concentration of detergent in the detergent solution is typically about 100 mM to about 2 M, preferably from about 200 mM to about 1.5 M.

The cationic lipids and plasmid will typically be combined to produce a charge ratio (+/-) of about 1:1 to about 20:1, preferably in a ratio of about 1:1 to about 12:1, and more preferably in a ratio of about 2:1 to about 6:1. Additionally, the overall concentration of plasmid in solution will typically be from about 25 μ g/mL to about 1 mg/mL, preferably from about 25 μ g/mL to about 200 μ g/mL, and more preferably from about 50 μ g/mL to about 100 μ g/mL. The combination of plasmids and cationic lipids in detergent solution is kept, typically at room temperature, for a period of time which is sufficient for the coated complexes to form. Alternatively, the plasmids and cationic

lipids can be combined in the detergent solution and warmed to temperatures of up to about 37°C. For plasmids which are particularly sensitive to temperature, the coated complexes can be formed at lower temperatures, typically down to about 4°C.

5 The detergent solution of the coated plasmid-lipid complexes is then contacted with non-cationic lipids to provide a detergent solution of plasmid-lipid complexes and non-cationic lipids. The non-cationic lipids which are useful in this step include, diacylphosphatidylcholine, diacylphosphatidylethanolamine, ceramide, sphingomyelin, cephalin, cardiolipin, and cerebroside. In preferred embodiments, the non-cationic lipids are diacylphosphatidylcholine, diacylphosphatidylethanolamine, 10 ceramide or sphingomyelin. The acyl groups in these lipids are preferably acyl groups derived from fatty acids having C₁₀-C₂₄ carbon chains. More preferably the acyl groups are lauroyl, myristoyl, palmitoyl, stearoyl or oleoyl. In particularly preferred embodiments, the non-cationic lipid will be 1,2-*sn*-dioleoylphosphatidylethanolamine (DOPE), palmitoyl oleoyl phosphatidylcholine (POPC) or egg phosphatidylcholine (EPC). In the most preferred embodiments, the plasmid-lipid particles will be fusogenic 15 particles with enhanced properties *in vivo* and the non-cationic lipid will be DOPE. In other preferred embodiments, the non-cationic lipids will further comprise polyethylene glycol-based polymers such as PEG 2000, PEG 5000 and polyethylene glycol conjugated to ceramides, as described in co-pending USSN 08/316,429, incorporated herein by reference.

20 The amount of non-cationic lipid which is used in the present methods is typically about 2 to about 20 mg of total lipids to 50 µg of plasmid. Preferably the amount of total lipid is from about 5 to about 10 mg per 50 µg of plasmid.

25 Following formation of the detergent solution of plasmid-lipid complexes and non-cationic lipids, the detergent is removed, preferably by dialysis. The removal of the detergent results in the formation of a lipid-bilayer which surrounds the plasmid providing serum-stable plasmid-lipid particles which have a size of from about 50 nm to about 150 nm. The particles thus formed do not aggregate and are optionally sized to achieve a uniform particle size.

30 The serum-stable plasmid-lipid particles can be sized by any of the methods available for sizing liposomes. The sizing may be conducted in order to achieve a desired size range and relatively narrow distribution of particle sizes.

Several techniques are available for sizing the particles to a desired size. One sizing method, used for liposomes and equally applicable to the present particles is

described in U.S. Pat. No. 4,737,323, incorporated herein by reference. Sonicating a particle suspension either by bath or probe sonication produces a progressive size reduction down to particles of less than about 50 nm in size. Homogenization is another method which relies on shearing energy to fragment larger particles into smaller ones.

5 In a typical homogenization procedure, particles are recirculated through a standard emulsion homogenizer until selected particle sizes, typically between about 60 and 80 nm, are observed. In both methods, the particle size distribution can be monitored by conventional laser-beam particle size discrimination, or QELS.

10 Extrusion of the particles through a small-pore polycarbonate membrane or an asymmetric ceramic membrane is also an effective method for reducing particle sizes to a relatively well-defined size distribution. Typically, the suspension is cycled through the membrane one or more times until the desired particle size distribution is achieved. The particles may be extruded through successively smaller-pore membranes, to achieve a gradual reduction in size.

15 In another group of embodiments, the present invention provides a method for the preparation of serum-stable plasmid-lipid particles, comprising;

- (a) preparing a mixture comprising cationic lipids and non-cationic lipids in an organic solvent;
- (b) contacting an aqueous solution of nucleic acid with said mixture in step (a) to provide a clear single phase; and
- 20 (c) removing said organic solvent to provide a suspension of plasmid-lipid particles, wherein said plasmid is encapsulated in a lipid bilayer, and said particles are stable in serum and have a size of from about 50 to about 150 nm.

25 The plasmids (or nucleic acids), cationic lipids and non-cationic lipids which are useful in this group of embodiments are as described for the detergent dialysis methods above.

30 The selection of an organic solvent will typically involve consideration of solvent polarity and the ease with which the solvent can be removed at the later stages of particle formation. The organic solvent, which is also used as a solubilizing agent, is in an amount sufficient to provide a clear single phase mixture of plasmid and lipids. Suitable solvents include chloroform, dichloromethane, diethylether, cyclohexane, cyclopentane, benzene, toluene, methanol, or other aliphatic alcohols such as propanol, isopropanol, butanol, tert-butanol, iso-butanol, pentanol and hexanol. Combinations of

two or more solvents may also be used in the present invention.

Contacting the plasmid with the organic solution of cationic and non-cationic lipids is accomplished by mixing together a first solution of plasmid, which is typically an aqueous solution and a second organic solution of the lipids. One of skill in the art will understand that this mixing can take place by any number of methods, for example by mechanical means such as by using vortex mixers.

After the plasmid has been contacted with the organic solution of lipids, the organic solvent is removed, thus forming an aqueous suspension of serum-stable plasmid-lipid particles. The methods used to remove the organic solvent will typically involve evaporation at reduced pressures or blowing a stream of inert gas (*e.g.*, nitrogen or argon) across the mixture.

The serum-stable plasmid-lipid particles thus formed will typically be sized from about 50 nm to 150 nm. To achieve further size reduction or homogeneity of size in the particles, sizing can be conducted as described above.

In other embodiments, the methods will further comprise adding nonlipid polycations which are useful to effect the transformation of cells using the present compositions. Examples of suitable nonlipid polycations include, hexadimethrine bromide (sold under the brandname POLYBRENE[®], from Aldrich Chemical Co., Milwaukee, Wisconsin, USA) or other salts of hexadimethrine. Other suitable polycations include, for example, salts of poly-L-ornithine, poly-L-arginine, poly-L-lysine, poly-D-lysine, polyallylamine and polyethyleneimine.

In other embodiments, the polyoxyethylene conjugates which are used in the plasmid-lipid particles of the present invention can be prepared by combining the conjugating group (*i.e.* phosphatidic acid or phosphatidylethanolamine) with an appropriately functionalized polyoxyethylene derivative. For example, phosphatidylethanolamine can be combined with polyoxyethylene bis(p-toluenesulfonate) to provide a phosphatidylethanolamine-polyoxyethylene conjugate. See, Woodle, *et al.*, *Biochim. Biophys. Acta* 1105:193-200 (1992), incorporated herein by reference.

In certain embodiments, the formation of the lipid-nucleic acid complexes can be carried out either in a monophasic system (*e.g.*, a Bligh and Dyer monophasic or similar mixture of aqueous and organic solvents) or in a two phase system with suitable mixing.

When formation of the complexes is carried out in a monophasic system, the cationic lipids and nucleic acids are each dissolved in a volume of the monophasic

mixture. Combination of the two solutions provides a single mixture in which the complexes form. Alternatively, the complexes can form in two-phase mixtures in which the cationic lipids bind to the nucleic acid (which is present in the aqueous phase), and "pull" it in to the organic phase.

5 Without intending to be bound by any particular theory of formation, Figure 1 provides a model for the binding of monocationic lipids to DNA which results in the formation of a hydrophobic (organic-soluble) lipid-nucleic acid complex. In this figure, cationic lipids first bind to the DNA to form a complex in which the DNA is uncondensed. This complex is soluble in the organic phase or in a monophase and the
10 DNA remains uncondensed. Upon the addition of other lipids and removal of solvent, and hydration, the complexes form particles (described in more detail below).

In another embodiment, the present invention provides a method for the preparation of lipid-nucleic acid particles, comprising:

- 15 (a) contacting nucleic acids with a solution comprising non-cationic lipids and a detergent to form a nucleic acid-lipid mixture;
- (b) contacting cationic lipids with the nucleic acid-lipid mixture to neutralize a portion of the negative charge of the nucleic acids and form a charge-neutralized mixture of nucleic acids and lipids; and
- 20 (c) removing the detergent from the charge-neutralized mixture to provide the lipid-nucleic acid particles in which the nucleic acids are protected from degradation.

Without intending to be limited by any particular aspect of the illustration, Figure 30 provides a depiction of one method of forming the particles using detergent dialysis. In this figure, DNA in an aqueous detergent solution (OGP) is combined with non-cationic lipids (ESM) in an aqueous detergent solution and allowed to anneal for
25 about 30 min. A previously sonicated mixture of cationic lipid (DODAC) in detergent is added and the resulting mixture is dialyzed for 3 days to remove detergent and thereby form lipid-nucleic acid particles. One of skill in the art will understand that for the kinetic formation of such particles, the order of addition of cationic lipids and non-cationic lipids could be reversed, or the lipids could be added simultaneously. In
30 addition, it is possible to cover the nucleic acid with multivalent cations, such that it now binds anions.

In one group of embodiments, the solution of non-cationic lipids and detergent is an aqueous solution. Contacting the nucleic acids with the solution of non-cationic lipids and detergent is typically accomplished by mixing together a first solution

of nucleic acids and a second solution of the lipids and detergent. One of skill in the art will understand that this mixing can take place by any number of methods, for example by mechanical means such as by using vortex mixers. Preferably, the nucleic acid solution is also a detergent solution. The amount of non-cationic lipid which is used in the present method is typically determined based on the amount of cationic lipid used, and is typically of from about 0.2 to 5 times the amount of cationic lipid, preferably about 0.5 to 2 times the amount of cationic lipid used.

The nucleic acid-lipid mixture thus formed is contacted with cationic lipids to neutralize a portion of the negative charge which is associated with the nucleic acids (or other polyanionic materials) present. The amount of cationic lipids used will typically be sufficient to neutralize at least 50% of the negative charge of the nucleic acid. Preferably, the negative charge will be at least 70% neutralized, more preferably at least 90% neutralized. Cationic lipids which are useful in the present invention, include, for example, DODAC, DOTMA, DDAB, DOTAP, DC-Chol and DMRIE. These lipids and related analogs have been described in co-pending USSN 08/316,399; U.S. Patent Nos. 5,208,036, 5,264,618, 5,279,833 and 5,283,185, the disclosures of which are incorporated herein by reference. Additionally, a number of commercial preparations of cationic lipids are available and can be used in the present invention. These include, for example, LIPOFECTIN® (commercially available cationic liposomes comprising DOTMA and DOPE, from GIBCO/BRL, Grand Island, New York, USA); LIPOFECTAMINE® (commercially available cationic liposomes comprising DOSPA and DOPE, from GIBCO/BRL); and TRANSFECTAM® (commercially available cationic lipids comprising DOGS in ethanol from Promega Corp., Madison, Wisconsin, USA).

Contacting the cationic lipids with the nucleic acid-lipid mixture can be accomplished by any of a number of techniques, preferably by mixing together a solution of the cationic lipid and a solution containing the nucleic acid-lipid mixture. Upon mixing the two solutions (or contacting in any other manner), a portion of the negative charge associated with the nucleic acid is neutralized. Nevertheless, the nucleic acid remains in an uncondensed state and acquires hydrophilic characteristics.

After the cationic lipids have been contacted with the nucleic acid-lipid mixture, the detergent (or combination of detergent and organic solvent) is removed, thus forming the lipid-nucleic acid particles. The methods used to remove the detergent will typically involve dialysis. When organic solvents are present, removal is typically accomplished by evaporation at reduced pressures or by blowing a stream of inert gas

(e.g., nitrogen or argon) across the mixture.

The particles thus formed will typically be sized from about 100 nm to several microns. To achieve further size reduction or homogeneity of size in the particles, the lipid-nucleic acid particles can be sonicated, filtered or subjected to other sizing techniques which are used in liposomal formulations and are known to those of skill in the art.

In other embodiments, the methods will further comprise adding nonlipid polycations which are useful to effect the lipofection of cells using the present compositions. Examples of suitable nonlipid polycations include, hexadimethrine bromide (sold under the brandname POLYBRENE®, from Aldrich Chemical Co., Milwaukee, Wisconsin, USA) or other salts of hexadimethrine. Other suitable polycations include, for example, salts of poly-L-ornithine, poly-L-arginine, poly-L-lysine, poly-D-lysine, polyallylamine and polyethyleneimine. Addition of these salts is preferably after the particles have been formed.

In another aspect, the present invention provides methods for the preparation of lipid-nucleic acid particles, comprising:

(a) contacting an amount of cationic lipids with nucleic acids in a solution; the solution comprising of from about 15-35% water and about 65-85% organic solvent and the amount of cationic lipids being sufficient to produce a +/- charge ratio of from about 0.85 to about 2.0, to provide a hydrophobic, charge-neutralized lipid-nucleic acid complex;

(b) contacting the hydrophobic, charge-neutralized lipid-nucleic acid complex in solution with non-cationic lipids, to provide a lipid-nucleic acid mixture; and

(c) removing the organic solvents from the lipid-nucleic acid mixture to provide lipid-nucleic acid particles in which the nucleic acids are protected from degradation.

The nucleic acids, non-cationic lipids, cationic lipids and organic solvents which are useful in this aspect of the invention are the same as those described for the methods above which used detergents. In one group of embodiments, the solution of step (a) is a monophasic. In another group of embodiments, the solution of step (a) is two-phase.

In preferred embodiments, the cationic lipids are DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS or combinations thereof. In other preferred embodiments, the non-cationic lipids are ESM, DOPE, polyethylene glycol-based

polymers (*e.g.*, PEG 2000, PEG 5000, PEG-modified phospholipids or PEG-modified ceramides) or combinations thereof. In still other preferred embodiments, the organic solvents are methanol, chloroform, methylene chloride, ethanol, diethyl ether or combinations thereof.

5 In a particularly preferred embodiment, the nucleic acid is a plasmid; the cationic lipid is DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS or combinations thereof; the non-cationic lipid is ESM, DOPE, polyethylene glycol-based polymers or combinations thereof; and the organic solvent is methanol, chloroform, methylene chloride, ethanol, diethyl ether or combinations thereof.

10 As above, contacting the nucleic acids with the cationic lipids is typically accomplished by mixing together a first solution of nucleic acids and a second solution of the lipids, preferably by mechanical means such as by using vortex mixers. The resulting mixture contains complexes as described for one aspect of the invention above. These complexes are then converted to particles by the addition of non-cationic lipids and
15 the removal of the organic solvent. The addition of the non-cationic lipids is typically accomplished by simply adding a solution of the non-cationic lipids to the mixture containing the complexes. A reverse addition can also be used. Subsequent removal of organic solvents can be accomplished by methods known to those of skill in the art and also described above.

20 The amount of non-cationic lipids which is used in this aspect of the invention is typically an amount of from about 0.2 to 5 times the amount (on a mole basis) of cationic lipids which was used to provide the charge-neutralized lipid-nucleic acid complex. Preferably, the amount is from 0.5 to 2 times the amount of cationic lipids used.

25 In yet another aspect, the present invention provides lipid-nucleic acid particles which are prepared by the methods described above. In these embodiments, the lipid-nucleic acid particles are either net charge neutral or carry an overall charge which provides the particles with greater gene lipofection activity. Preferably, the nucleic acid component of the particles is a nucleic acid which encodes a desired protein or blocks the
30 production of an undesired protein. In particularly preferred embodiments, the nucleic acid is a plasmid, the non-cationic lipid is egg sphingomyelin and the cationic lipid is DODAC.

As noted above, the lipid-nucleic acid particles are useful for the lipofection of cells, either *in vitro* or *in vivo*. Accordingly, the present invention

provides, in yet another aspect, a method for introducing a nucleic acid into a cell, comprising;

- (a) preparing a lipid-nucleic acid particle according to the methods above; and
 - (b) contacting the cell with the lipid-nucleic acid particle for a period of time
- 5 sufficient to introduce the nucleic acid into the cell.

Although discussed in more detail below, preferred embodiments are those in which the lipid-nucleic acid particle comprises a plasmid, DODAC and ESM.

Unlike viral-based gene therapy vectors which can only incorporate a relatively small non-viral nucleic acid sequence into the viral genome because of size limitations for packaging virion particles, the lipid-nucleic acid complexes of the present invention may be used to transfer large (*e.g.*, 50-5,000 kilobase) exogenous nucleic acids into cells. This aspect of lipofection is particularly advantageous since many genes which may be targets for gene therapy span over 100 kilobases (*e.g.*, amyloid precursor protein (APP) gene, Huntington's chorea gene) and large homologous targeting constructs or transgenes may be required for therapy.

Cells can be lipofected with an exogenous nucleic acid at high efficiency and with cell type specificity by contacting the cells with a receptor-recognition transfection complex comprising: (1) an exogenous nucleic acid, (2) a receptor-ligand protein ("rlp") which is covalently linked to a polycation, and (3) a cationic or neutral lipid. It has been found that a combination of a polycation-linked receptor-recognition protein and a suitable cationic (or neutral) lipid can be used to transfect nucleic acids, and that the combination retains cell type targeting specificity conferred by the receptor-recognition protein and also exhibits high efficiency transfection conferred, in part, by the inclusion of a cationic lipid, neutral lipid, or lipopolyamine.

25 The exogenous nucleic acid is typically dsDNA, ssDNA, ssRNA, dsRNA; most typically the exogenous nucleic acid is dsDNA such as a cloned DNA sequence in a cloning vector such as a plasmid or viral genome. Multiple species of exogenous nucleic acid may be combined in a transfection complex, such as for co-transfection of unlinked nucleic acid sequences or to accomplish *in vivo* homologous recombination shuffling. Frequently, the exogenous nucleic acid(s) are not capable of autonomous replication in cells which incorporate the transfection complex, and are either transiently expressed or are stably integrated into a host cell chromosome by homologous recombination or nonhomologous integration. Often at least one selectable marker (*e.g.*, a *neo^R* expression cassette) is included in the exogenous nucleic acid(s) to facilitate selection of cells which

30

have incorporated the exogenous nucleic acid(s). Typically, an exogenous nucleic acid comprises a structural gene encoding a polypeptide to be expressed in a target cell which has incorporated the exogenous nucleic acid, and the structural gene usually is operably linked to appropriate cis-acting regulatory elements (*e.g.*, promoter, enhancer, polyadenylation site). Although gene therapy may be performed in a variety of ways, a typical receptor-recognition lipofection complex comprises a nucleic acid which comprises at least one transcriptional unit.

The lipid nucleic acid particles of the invention can be designed to contain, in addition to the species of nucleic acid, a receptor-recognition molecule (rlm), such as a protein. The rlm can be covalently bound to lipids that comprise the nucleic acid-lipid particle. Its presence on the particle increases the efficiency and specificity with the particle contacts and enters target cells. For example, a suitable rlm is a non-immunoglobulin protein that binds to a cell surface receptor of a target cell which mediates internalization of a transfection complex comprising the rlm-polycation conjugate by, for example, the process of endocytosis and/or membrane fusion. Additional suitable rlm species typically are naturally-occurring physiological ligands which comprise a polypeptide portion (*e.g.*, adhesion molecules such as ICAM-1, ICAM-2, ELAM-1, VCAM-1). Viral proteins (*e.g.*, spike glycoproteins) which bind to viral receptors on eukaryotic cells and mediate virus internalization may also be used as rlm species for forming rlm-polycation conjugates. Examples also include viral glycoproteins which attach to cell surface receptors and lead to internalization and/or membrane fusion include the gB, gC, gD, gE, gH, and gI virion glycoproteins of HSV-1, and gp120 of HIV-1.

Fragments and analogs of naturally-occurring proteins may be used as well as full-length mature proteins as rlm species in forming transfection complexes of the invention. For example, fragments, analogs, and fusion proteins comprising a portion of an adhesion molecule or virion attachment protein which mediates attachment to a target cell may be used as rlm species without other portions of the naturally-occurring full-length protein that are not essential for cell attachment and/or membrane fusion. Thus, for example, a cytoplasmic tail peptide portion of a virion glycoprotein usually may be omitted and the resultant protein may still serve as a suitable rlm.

The rlm selected will vary with the particular target cell type. For specific targeting to hepatocytes, asialoglycoproteins (galactose-terminal) are preferred as rlm species. Examples of asialoglycoproteins include asialoorosomucoid, asialofetuin, and

desialylated vesicular stomatitis virus virion proteins. These can be formed by chemical or enzymatic desialylation of those glycoproteins that possess terminal sialic acid and penultimate galactose residues. Alternatively, rlm species suitable for forming lipofection complexes that selectively target hepatocytes may be created by coupling
5 lactose or other galactose-terminal carbohydrates (*e.g.*, arabinogalactan) to non-galactose-bearing proteins by reductive lactosamination. Other useful galactose-terminal carbohydrates for hepatocyte targeting include carbohydrate trees obtained from natural glycoproteins, especially tri- and tetra-antennary structures that contain either terminal galactose residues or that can be enzymatically treated to expose terminal galactose
10 residues. For targeting macrophages, endothelial cells, or lymphocytes, rlm species comprising mannose or mannose-6-phosphate, or complex carbohydrates comprising these terminal carbohydrate structures may be used.

Since a variety of different cell surface receptors exist on the surfaces of mammalian cells, cell-specific targeting of nucleic acids to nonhepatic cells can involve
15 lipofection complexes that comprise various rlm species. For example, transferrin can be used as a suitable rlm for forming receptor-recognition transfection complexes to cells expressing transferrin receptors. Other receptor ligands such as polypeptide hormones (*e.g.*, growth hormone, PDGF, FGF, EGF, insulin, IL-2, IL-4, etc.) may be used to localize receptor-recognition transfection complexes to cells expressing the cognate
20 receptor.

The nucleic acid-lipid particles may comprise multiple rlm species. Frequently, an agent having membrane fusion activity (*e.g.*, influenza virus hemagglutinin, HSV-1 gB and gD) is used as an rlm for forming rlm-polycation
25 complexes, either alone or in combination with other rlm species, typically with those which lack membrane fusion activity.

These transfection methods generally comprise the steps of: (1) forming a nucleic acid-lipid-rlm particle consisting essentially of an exogenous nucleic acid, a polycation conjugate consisting essentially of a polycation linked to a non-immunoglobulin receptor-recognition molecule that binds to a predetermined cell surface
30 receptor, and a lipid component consisting essentially of a neutral or cationic lipid (optionally including a quaternary ammonium detergent and/or a lipopolyamine), and (2) contacting cells expressing the predetermined cell surface receptor with a composition comprising the receptor-recognition transfection complex under physiological transfection conditions which permit uptake of the exogenous nucleic acid into said cells. In

alternative embodiments, the rim is attached to the polycation by covalent linkage, frequently by covalent linkage through a crosslinking agent or by peptide linkage.

Overall particle charge is an important property of the particles, as it may affect particle clearance from the blood. Particles with prolonged circulation half-lives are typically desirable for therapeutic and diagnostic uses. For instance, particles which can be maintained from 8, 12, or up to 24 hours in the bloodstream are particularly preferred. Negatively charged liposomes and particles are typically, taken up more rapidly by the reticuloendothelial system (Juliano, *Biochem. Biophys. Res. Commun.* 63:651 (1975)) and thus have shorter half-lives in the bloodstream.

C. Pharmaceutical Preparations

The nucleic acid-lipid particles of the present invention can be administered either alone or in mixture with a physiologically-acceptable carrier (such as physiological saline or phosphate buffer) selected in accordance with the route of administration and standard pharmaceutical practice. Generally, normal saline will be employed as the pharmaceutically acceptable carrier. Other suitable carriers include, *e.g.*, water, buffered water, 0.4% saline, 0.3% glycine, and the like, including glycoproteins for enhanced stability, such as albumin, lipoprotein, globulin, *etc.*

The pharmaceutical carrier is generally added following particle formation. Thus, after the particle is formed, the particle can be diluted into pharmaceutically acceptable carriers such as normal saline.

The concentration of particles in the pharmaceutical formulations can vary widely, *i.e.*, from less than about 0.05%, usually at or at least about 2-5% to as much as 10 to 30% by weight and will be selected primarily by fluid volumes, viscosities, *etc.*, in accordance with the particular mode of administration selected. For example, the concentration may be increased to lower the fluid load associated with treatment. This may be particularly desirable in patients having atherosclerosis-associated congestive heart failure or severe hypertension. Alternatively, particles composed of irritating lipids may be diluted to low concentrations to lessen inflammation at the site of administration. It is often desirable to include polyethylene glycol (PEG), PEG-ceramide, or modified (*e.g.*, ganglioside G_{M1} -modified) lipids to the particles. Addition of such components prevents particle aggregation and provides a means for increasing circulation lifetime and increasing the delivery of the lipid-nucleic acid particles to the target tissues. Typically, the concentration of the PEG, PEG-ceramide or G_{M1} -modified lipids in the particle will be about 1-15%.

The pharmaceutical compositions may be sterilized by conventional, well known sterilization techniques. Aqueous solutions can be packaged for use or filtered under aseptic conditions and lyophilized, the lyophilized preparation being combined with a sterile aqueous solution prior to administration. The compositions can contain pharmaceutically acceptable auxiliary substances as required to approximate physiological conditions, such as pH adjusting and buffering agents, tonicity adjusting agents and the like, for example, sodium acetate, sodium lactate, sodium chloride, potassium chloride, and calcium chloride. Additionally, the particle suspension may include lipid-protective

agents which protect lipids against free-radical and lipid-peroxidative damages on storage. Lipophilic free-radical quenchers, such as alphotocopherol and water-soluble iron-specific chelators, such as ferrioxamine, are suitable.

5 In another example of their use, lipid-nucleic acid particles can be incorporated into a broad range of topical dosage forms including but not limited to gels, oils, emulsions and the like. For instance, the suspension containing the nucleic acid-lipid particles can be formulated and administered as topical creams, pastes, ointments, gels, lotions and the like.

10 The present invention also provides lipid-nucleic acid particles in kit form. The kit will typically be comprised of a container which is compartmentalized for holding the various elements of the kit. The kit will contain the compositions of the present inventions, preferably in dehydrated form, with instructions for their rehydration and administration. In still other embodiments, the particles and/or compositions comprising the particles will have a targeting moiety attached to the surface of the
15 particle. Methods of attaching targeting moieties (e.g., antibodies, proteins) to lipids (such as those used in the present particles) are known to those of skill in the art.

D. Administration of Lipid-Nucleic Acid Particle Formulations

The serum-stable nucleic acid-lipid particles of the present invention are useful for the introduction of nucleic acids into cells. Accordingly, the present invention
20 also provides methods for introducing a nucleic acids (e.g., a plasmid) into a cell. The methods are carried out *in vitro* or *in vivo* by first forming the particles as described above, then contacting the particles with the cells for a period of time sufficient for transfection to occur.

25 The nucleic acid-lipid particles of the present invention can be adsorbed to almost any cell type with which they are mixed or contacted. Once adsorbed, the particles can either be endocytosed by a portion of the cells, exchange lipids with cell membranes, or fuse with the cells. Transfer or incorporation of the nucleic acid portion of the particle can take place via any one of these pathways. In particular, when fusion takes place, the particle membrane is integrated into the cell membrane and the contents
30 of the particle combine with the intracellular fluid.

1. *In vitro* gene transfer

For *in vitro* applications, the delivery of nucleic acids can be to any cell grown in culture, whether of plant or animal origin, vertebrate or invertebrate, and of any tissue or type. In preferred embodiments, the cells will be animal cells, more preferably mammalian cells, and most preferably human cells.

Contact between the cells and the lipid-nucleic acid particles, when carried out *in vitro*, takes place in a biologically compatible medium. The concentration of particles varies widely depending on the particular application, but is generally between about 1 μ mol and about 10 mmol. Treatment of the cells with the nucleic acid-lipid particles is generally carried out at physiological temperatures (about 37° C) for periods of time of from about 1 to 48 hours, preferably of from about 2 to 4 hours.

In one group of preferred embodiments, a lipid-nucleic acid particle suspension is added to 60-80% confluent plated cells having a cell density of from about 10^3 to about 10^5 cells/mL, more preferably about 2×10^4 cells/mL. The concentration of the suspension added to the cells is preferably of from about 0.01 to 0.2 μ g/mL, more preferably about 0.1 μ g/mL.

2. *In vivo* gene transfer

Alternatively, the compositions of the present invention can also be used for the *in vivo* gene transfer, using methods which are known to those of skill in the art. In particular, Zhu, *et al.*, Science 261:209-211 (1993), incorporated herein by reference, describes the intravenous delivery of cytomegalovirus (CMV)-chloramphenicol acetyltransferase (CAT) expression plasmid using DOTMA-DOPE complexes. Hyde, *et al.*, Nature 362:250-256 (1993), incorporated herein by reference, describes the delivery of the cystic fibrosis transmembrane conductance regulator (CFTR) gene to epithelia of the airway and to alveoli in the lung of mice, using liposomes. Brigham, *et al.*, Am. J. Med. Sci. 298:278-281 (1989), incorporated herein by reference, describes the *in vivo* transfection of lungs of mice with a functioning prokaryotic gene encoding the intracellular enzyme chloramphenicol acetyltransferase (CAT).

For *in vivo* administration, the pharmaceutical compositions are preferably administered parenterally, *i.e.*, intraarticularly, intravenously, intraperitoneally, subcutaneously, or intramuscularly. More preferably, the pharmaceutical compositions are administered intravenously or intraperitoneally by a bolus injection. For example, see Stadler, *et al.*, U.S. Patent No. 5,286,634, which is incorporated herein by

reference. Intracellular nucleic acid delivery has also been discussed in Straubinger, *et al.*, METHODS IN ENZYMOLOGY, Academic Press, New York. 101:512-527 (1983); Mannino, *et al.*, Biotechniques 6:682-690 (1988); Nicolau, *et al.*, Crit. Rev. Ther. Drug Carrier Syst. 6:239-271 (1989), and Behr, *Acc. Chem. Res.* 26:274-278 (1993). Still
5 other methods of administering lipid-based therapeutics are described in, for example, Rahman *et al.*, U.S. Patent No. 3,993,754; Sears, U.S. Patent No. 4,145,410; Papahadjopoulos *et al.*, U.S. Patent No. 4,235,871; Schneider, U.S. Patent No. 4,224,179; Lenk *et al.*, U.S. Patent No. 4,522,803; and Fountain *et al.*, U.S. Patent No. 4,588,578.

10 In certain embodiments, the pharmaceutical preparations may be contacted with the target tissue by direct application of the preparation to the tissue. The application may be made by topical, "open" or "closed" procedures. By "topical", it is meant the direct application of the pharmaceutical preparation to a tissue exposed to the environment, such as the skin, oropharynx, external auditory canal, and the like.
15 "Open" procedures are those procedures which include incising the skin of a patient and directly visualizing the underlying tissue to which the pharmaceutical preparations are applied. This is generally accomplished by a surgical procedure, such as a thoracotomy to access the lungs, abdominal laparotomy to access abdominal viscera, or other direct surgical approach to the target tissue. "Closed" procedures are invasive procedures in
20 which the internal target tissues are not directly visualized, but accessed via inserting instruments through small wounds in the skin. For example, the preparations may be administered to the peritoneum by needle lavage. Likewise, the pharmaceutical preparations may be administered to the meninges or spinal cord by infusion during a lumbar puncture followed by appropriate positioning of the patient as commonly
25 practiced for spinal anesthesia or metrazamide imaging of the spinal cord. Alternatively, the preparations may be administered through endoscopic devices.

The lipid-nucleic acid particles can also be administered in an aerosol inhaled into the lungs (see, Brigham, *et al.*, Am. J. Sci. 298(4):278-281 (1989)) or by direct injection at the site of disease (Culver, HUMAN GENE THERAPY, MaryAnn Liebert, Inc., Publishers, New York. pp.70-71 (1994)).
30

The methods of the present invention may be practiced in a variety of hosts. Preferred hosts include mammalian species, such as humans, non-human primates, dogs, cats, cattle, horses, sheep, and the like.

The amount of particles administered will depend upon the the ratio of

nucleic acid to lipid; the particular nucleic acid used, the disease state being diagnosed; the age, weight, and condition of the patient and the judgement of the clinician; but will generally be between about 0.01 and about 50 mg per kilogram of body weight; preferably between about 0.1 and about 5 mg/kg of body weight or about 10^8 - 10^{10} particles per injection.

3. Insertion of Functional Copy of a Gene

Some methods of gene therapy serve to compensate for a defect in an endogenous gene by integrating a functional copy of the gene into the host chromosome. The inserted gene replicates with the host DNA and is expressed at a level to compensate for the defective gene. Diseases amenable to treatment by this approach are often characterized by recessive mutations. That is, both copies of an endogenous gene must be defective for symptoms to appear. Such diseases include cystic fibrosis, sickle cell anemia, β -thalassemia, phenylketonuria, galactosemia, Wilson's disease, hemochromatosis, severe combined immunodeficiency disease, alpha-1-antitrypsin deficiency, albinism, alkaptonuria, lysosomal storage diseases, Ehlers-Danlos syndrome, hemophilia, glucose-6-phosphate dehydrogenase deficiency, agammaglobulinemia, diabetes insipidus, Lesch-Nyhan syndrome, muscular dystrophy, Wiskott-Aldrich syndrome, Fabry's disease, fragile X-syndrome, and the like. Other recessive mutations are known in the art, and the use of the methods of the present invention to treat them is contemplated herein.

There are several methods for introducing an exogenous functional gene to compensate for the above genetic defects. In one approach, cells are removed from a patient suffering from the disease and contacted with a lipid-vector complex *in vitro*. Cells should be removed from a tissue type in which disease symptoms are manifested. If the cells are capable of replication, and the vector used includes a selective marker, cells having internalized and expressed the marker can be selected. Particularly if selection is not performed, it is important that the frequency of gene transfer into cells be high, for example, at least about 1, 5, 10, 25 or 50% of cells.

After integration of the vector into the cellular genome, and optionally, selection, cells are reintroduced into the patient. In this application, and others discussed below (except site-specific recombination to correct dominant mutations), it is not necessary that the gene supplied by the lipid-nucleic acid particle be delivered to the same site as is occupied by the defective gene for which it is compensating.

Alternatively, the lipid-vector complex can be introduced directly into a patient as a pharmaceutical composition. The complex is delivered to the tissue(s) affected by the genetic disorder being treated in a therapeutically effective dose. In this and other methods, a therapeutically effective dose is an amount sufficient to cure, or at least partially arrest, the symptoms of the disease and its complications. Effective doses of the compositions of the present invention, for the treatment of the above described conditions will vary depending upon many different factors, including means of administration, target site, physiological state of the patient, and other medicants administered. Thus, treatment dosages will need to be titrated to optimize safety and efficacy. Doses ranging from about 10 ng to 1 g, 100 ng to 100 mg, 1 μ g to 10 mg, or 30-300 μ g DNA per patient are typical. Routes of administration include oral, nasal, gastric, intravenous, intradermal and intramuscular.

The nucleic acid-lipid complexes can also be used to transfect embryonic stem cells or zygotes to achieve germline alterations. See Jaenisch, *Science*, 240, 1468-1474 (1988); Gordon *et al.* (1984) *Methods Enzymol.* 101, 414; Hogan *et al.*, *Manipulation of the Mouse Embryo: A Laboratory Manual*, C.S.H.L. N.Y. (1986); and Hammer *et al.* (1985) *Nature* 315, 680; Gandolfi *et al.* (1987) *J. Reprod. Fert.* 81, 23-28; Rexroad *et al.* (1988) *J. Anim. Sci.* 66, 947-953 and Eyestone *et al.* (1989) *J. Reprod. Fert.* 85, 715-720; Camous *et al.* (1984) *J. Reprod. Fert.* 72, 779-785; Heyman *et al.* (1987) *Theriogenology* 27, 5968. However, these methods are presently more suitable for veterinary applications than human treatment due to ethical and regulatory constraints in manipulating human embryos.

As an example, cystic fibrosis (CF) is a usually fatal recessive genetic disease, having a high incidence in Caucasian populations. The gene responsible for this disease was isolated by Riordan *et al.*, *Science* 245, 1059-1065 (1989). It encodes a protein called the cystic fibrosis transmembrane conductance regulator (CFTR) which is involved in the transfer of chloride ions (Cl^-) through epithelial cell membranes. Mutations in the gene cause defects of Cl^- secretion in epithelial cells leading to the various clinical manifestations. Although CF has a number of symptoms including thickened exocrine gland secretions, pancreatic deficiency, intestinal blockage and malabsorption of fat, the most serious factor affecting mortality is chronic lung disease. Accordingly, to treat a CF patient, a vector containing a coding sequence for a functional CFTR gene product can be complexed with lipid, and optionally, a pharmaceutical excipient and introduced into the patient via nasal administration so that the vector-lipid

composition reaches the lungs. The dose of vector-lipid complex is preferably about 10^8 - 10^{10} particles.

As another example, defects in the α or γ globin genes (see McDonagh & Nienhuis in *Hematology of Infancy and Childhood* (eds. Nathan & Oski, Saunders, PA, 1992) at pp. 783-879) can be compensated for by *ex vivo* treatment of hemopoietic stem cells with an nucleic acid-lipid complex containing a functional copy of the gene. The gene integrates into the stem cells which are then reintroduced into the patient. Defects in the gene responsible for Fanconi Anemia Complement Group C can be treated by an analogous strategy (see Walsh *et al.*, *J. Clin. Invest.* 94, 1440-1448 (1994)).

Other applications include the introduction of a functional copy of a tumor suppressor gene into cancerous cell or cells at risk of becoming cancerous. Individuals having defects in one or both copies of an endogenous tumor suppressor gene are particularly at risk of developing cancers. For example, Li-Fraumeni syndrome is a hereditary condition in which individuals receive mutant p53 alleles, resulting in the early onset of various cancers (Harris, *Science* 262, 1980-1981 (1993) Frebourg *et al.*, *PNAS* 89, 6413-6417 (1992); Malkin *et al.*, *Science* 250, 1233 (1990)). Expression of a tumor suppressor gene in a cancerous cell or a cell at risk of becoming cancerous is effective to prevent, arrest and/or reverse cellular proliferation and other manifestations of the cancerous state. Suitable tumor suppressor genes for use in the invention include p53 (Buchman *et al.*, *Gene* 70, 245-252 (1988)), APC, DCC, Rb, WT1, and NF1 (Marx, *Science* 260, 751-752 (1993); Marshall, *Cell* 64, 313-326 (1991)). Lipid-nucleic acid complexes bearing a functional copy of a tumor suppressor gene are usually administered *in vivo* by the route most proximal to the intended site of action. For example, skin cancers can be treated by topical administration and leukemia by intravenous administration.

4. Suppression of Gene Expression

Methods of gene therapy using the nucleic acid-lipid complexes of the invention can also be used for prophylactic or therapeutic treatment of patients or cells, infected with or at risk of being infected with, a pathogenic microorganism, such as HIV. The effectiveness of antisense molecules in blocking target gene functions of impeding virus replication has been demonstrated in a number of different systems (Friedman *et al.*, *Nature* 335, 452-54 (1988), Malim *et al.*, *Cell* 58, 205-14 (1989) & Trono *et al.*, *Cell* 59, 113-20 (1989)). The vector used includes a DNA segment

encoding an antisense transcript, which is complementary to a segment of the genome from the pathogenic microorganism. The segment should preferably play an essential role in the lifecycle of the microorganism, and should also be unique to the microorganism (or at least absent from the genome of the natural genome of a patient undergoing therapy). For example, suitable sites for inhibition on the HIV virus includes TAR, REV or nef (Chatterjee *et al.*, *Science* 258, 1485-1488 (1992)). Rev is a regulatory RNA binding protein that facilitates the export of unspliced HIV pre mRNA from the nucleus. Malim *et al.*, *Nature* 338, 254 (1989). Tat is thought to be a transcriptional activator that functions by binding a recognition sequence in 5' flanking mRNA. Karn & Graeble, *Trends Genet.* 8, 365 (1992). The nucleic acid-lipid complex is introduced into leukocytes or hemopoietic stem cells, either *ex vivo* or by intravenous injection in a therapeutically effective dose. The treatment can be administered prophylactically to HIV⁺ persons, or to persons already infected with HIV.

Analogous methods are used for suppressing expression of endogenous recipient cell genes encoding adhesion proteins. Suppression of adhesion protein expression is useful in aborting undesirable inflammatory responses. Adhesion proteins that can be suppressed by antisense segments present in selected vectors include integrins, selectins, and immunoglobulin (Ig) superfamily members (*see* Springer, *Nature* 346, 425-433 (1990). Osborn, *Cell* 62, 3 (1990); Hynes, *Cell* 69, 11 (1992)). Integrins are heterodimeric transmembrane glycoproteins consisting of an α chain (120-180 kDa) and a β chain (90-110 kDa), generally having short cytoplasmic domains. The three known integrins, LFA-1, Mac-1 and P150,95, have different alpha subunits, designated CD11a, CD11b and CD11c, and a common beta subunit designated CD18. LFA-1 ($\alpha_L\beta_2$) is expressed on lymphocytes, granulocyte and monocytes, and binds predominantly to an Ig-family member counter-receptor termed ICAM-1 (and perhaps to a lesser extent ICAM-2). ICAM-1 is expressed on many cells, including leukocytes and endothelial cells, and is up-regulated on vascular endothelium by cytokines such as TNF and IL-1. Mac-1 ($\alpha_M\beta_2$) is distributed on neutrophils and monocytes, and also binds to ICAM-1 (and possibly ICAM-2). The third β_2 integrin, P150,95 ($\alpha_X\beta_2$), is also found on neutrophils and monocytes. The selectins consist of L-selectin, E-selectin and P-selectin.

5. Cells to be transformed

The compositions and methods of the present invention are used to treat a

wide variety of cell types, *in vivo* and *in vitro*. Among those most often targeted for gene therapy are hematopoietic precursor (stem) cells. Other cells include those of which a proportion of the targeted cells are nondividing or slow dividing. These include, for example, fibroblasts, keratinocytes, endothelial cells, skeletal and smooth muscle cells, osteoblasts, neurons, quiescent lymphocytes, terminally differentiated cells, slow or non-cycling primary cells, parenchymal cells, lymphoid cells, epithelial cells, bone cells, etc. The methods and compositions can be employed with cells of a wide variety of vertebrates, including mammals, and especially those of veterinary importance, e.g., canine, feline, equine, bovine, ovine, caprine, rodent, lagomorph, swine, etc., in addition to human cell populations.

To the extent that tissue culture of cells may be required, it is well known in the art. Freshney (1994) (*Culture of Animal Cells, a Manual of Basic Technique, third edition* Wiley-Liss, New York), Kuchler *et al.* (1977) *Biochemical Methods in Cell Culture and Virology*, Kuchler, R.J., Dowden, Hutchinson and Ross, Inc., and the references cited therein provides a general guide to the culture of cells. Cultured cell systems often will be in the form of monolayers of cells, although cell suspensions are also used.

Gene therapy relies on the efficient delivery of therapeutic genes to target cells. Most of the somatic cells that have been targeted for gene therapy, e.g., hematopoietic cells, skin fibroblasts and keratinocytes, hepatocytes, endothelial cells, muscle cells and lymphocytes, are normally non-dividing. Retroviral vectors, which are the most widely used vectors for gene therapy, unfortunately require cell division for effective transduction (Miller *et al.*, Mol. Cell. Biol. 10:4239-4242 (1990)). This is also true with other gene therapy vectors such as the adeno-associated vectors (Russell *et al.*, Proc. Natl. Acad. Sci. USA 91: 8915-8919 (1994); Alexander *et al.*, J. Virol. 68: 8282-8287 (1994); Srivastava, Blood Cells 20: 531-538 (1994)). Recently, HIV-based vectors has been reported to transfect non-dividing cells (CITE). Nonetheless, the majority of stem cells, a preferred target for many gene therapy treatments, are normally not proliferating. Thus, the efficiency of transduction is often relatively low, and the gene product may not be expressed in therapeutically or prophylactically effective amounts. This has led investigators to develop techniques such as stimulating the stem cells to proliferate prior to or during gene transfer (e.g., by treatment with growth factors) pretreatment with 5-fluorouracil, infection in the presence of cytokines, and extending the vector infection period to increase the likelihood that stem cells are dividing during

infection, but these have met with limited success.

6. Detection of foreign nucleic acids

After a given cell is transduced with a nucleic acid construct that encodes a gene of interest, it is important to detect which cells or cell lines express the gene product and to assess the level of expression of the gene product in engineered cells. This requires the detection of nucleic acids that encode the gene products.

Nucleic acids and proteins are detected and quantified herein by any of a number of means well known to those of skill in the art. These include analytic biochemical methods such as spectrophotometry, radiography, electrophoresis, capillary electrophoresis, high performance liquid chromatography (HPLC), thin layer chromatography (TLC), hyperdiffusion chromatography, and the like, and various immunological methods such as fluid or gel precipitin reactions, immunodiffusion (single or double), immunoelectrophoresis, radioimmunoassays (RIAs), enzyme-linked immunosorbent assays (ELISAs), immunofluorescent assays, and the like. The detection of nucleic acids proceeds by well known methods such as Southern analysis, northern analysis, gel electrophoresis, PCR, radiolabeling, scintillation counting, and affinity chromatography.

The selection of a nucleic acid hybridization format is not critical. A variety of nucleic acid hybridization formats are known to those skilled in the art. For example, common formats include sandwich assays and competition or displacement assays. Hybridization techniques are generally described in "*Nucleic Acid Hybridization, A Practical Approach*," Ed. Hames, B.D. and Higgins, S.J., IRL Press, 1985.

The sensitivity of the hybridization assays may be enhanced through use of a nucleic acid amplification system which multiplies the target nucleic acid being detected. *In vitro* amplification techniques suitable for amplifying sequences for use as molecular probes or for generating nucleic acid fragments for subsequent subcloning are known. Examples of techniques sufficient to direct persons of skill through such *in vitro* amplification methods, including the polymerase chain reaction (PCR) the ligase chain reaction (LCR), Q β -replicase amplification and other RNA polymerase mediated techniques (*e.g.*, NASBA) are found in Berger, Sambrook, and Ausubel, as well as Mullis *et al.* (1987), U.S. Patent No. 4,683,202; *PCR Protocols A Guide to Methods and Applications* (Innis *et al.* eds) Academic Press Inc. San Diego, CA (1990) (Innis);

Arnheim & Levinson (October 1, 1990), *C&EN* 36-47; *The Journal Of NIH Research* (1991), 3: 81-94; (Kwoh *et al.* (1989), *Proc. Natl. Acad. Sci. USA*, 86: 1173; Guatelli *et al.* (1990), *Proc. Natl. Acad. Sci. USA*, 87: 1874; Lomell *et al.* (1989), *J. Clin. Chem.*, 35: 1826; Landegren *et al.* (1988), *Science*, 241: 1077-1080; Van Brunt (1990),
5 *Biotechnology*, 8: 291-294; Wu and Wallace (1989), *Gene*, 4: 560; Barringer *et al.* (1990), *Gene*, 89: 117, and Souknanan and Malek (1995), *Biotechnology*, 13: 563-564. Improved methods of cloning *in vitro* amplified nucleic acids are described in Wallace *et al.*, U.S. Pat. No. 5,426,039. Other methods recently described in the art are the
10 nucleic acid sequence based amplification (NASBA™, Cangene, Mississauga, Ontario) and Q Beta Replicase systems. These systems can be used to directly identify mutants where the PCR or LCR primers are designed to be extended or ligated only when a select sequence is present. Alternatively, the select sequences can be generally amplified using, for example, nonspecific PCR primers and the amplified target region later probed for a specific sequence indicative of a mutation.

15 Oligonucleotides for use as probes, *e.g.*, in *in vitro* amplification methods, for use as gene probes, or as inhibitor components are typically synthesized chemically according to the solid phase phosphoramidite triester method described by Beaucage and Caruthers (1981), *Tetrahedron Letts.*, 22(20): 1859-1862, *e.g.*, using an automated
20 synthesizer, as described in Needham-VanDevanter *et al.* (1984), *Nucleic Acids Res.*, 12: 6159-6168. Purification of oligonucleotides, where necessary, is typically performed by either native acrylamide gel electrophoresis or by anion-exchange HPLC as described in Pearson and Regnier (1983), *J. Chrom.*, 255: 137-149. The sequence of the synthetic oligonucleotides can be verified using the chemical degradation method of Maxam and
25 Gilbert (1980) in Grossman and Moldave (eds.) Academic Press, New York, *Methods in Enzymology*, 65: 499-560.

30 An alternative means for determining the level of expression of the gene is *in situ* hybridization. *In situ* hybridization assays are well known and are generally described in Angerer *et al.* (1987), *Methods Enzymol.*, 152: 649-660. In an *in situ* hybridization assay cells are fixed to a solid support, typically a glass slide. If DNA is to be probed, the cells are denatured with heat or alkali. The cells are then contacted with a hybridization solution at a moderate temperature to permit annealing of specific probes that are labelled. The probes are preferably labelled with radioisotopes or fluorescent reporters.

7. Detection of foreign gene products

The expression of the gene of interest to produce a product may be detected or quantified by a variety of methods. Preferred methods involve the use of specific antibodies.

5 Methods of producing polyclonal and monoclonal antibodies are known to those of skill in the art. *See, e.g.*, Coligan (1991), CURRENT PROTOCOLS IN IMMUNOLOGY, Wiley/Greene, NY; and Harlow and Lane (1989), ANTIBODIES: A LABORATORY MANUAL, Cold Spring Harbor Press, NY; Stites *et al.* (eds.) BASIC AND CLINICAL IMMUNOLOGY (4th ed.) Lange Medical Publications, Los Altos, CA, and
10 references cited therein; Goding (1986), MONOCLONAL ANTIBODIES: PRINCIPLES AND PRACTICE (2d ed.) Academic Press, New York, NY; and Kohler and Milstein (1975), *Nature*, 256: 495-497. Such techniques include antibody preparation by selection of antibodies from libraries of recombinant antibodies in phage or similar vectors. *See*, Huse *et al.* (1989), *Science*, 246: 1275-1281; and Ward *et al.* (1989), *Nature*, 341:
15 544-546. Specific monoclonal and polyclonal antibodies and antisera will usually bind with a K_D of at least about .1 mM, more usually at least about 1 μ M, preferably at least about .1 μ M or better, and most typically and preferably, .01 μ M or better.

The presence of a desired polypeptide (including peptide, transcript, or enzymatic digestion product) in a sample may be detected and quantified using Western
20 blot analysis. The technique generally comprises separating sample products by gel electrophoresis on the basis of molecular weight, transferring the separated proteins to a suitable solid support, (such as a nitrocellulose filter, a nylon filter, or derivatized nylon filter), and incubating the sample with labeling antibodies that specifically bind to the analyte protein. The labeling antibodies specifically bind to analyte on the solid support.
25 These antibodies are directly labeled, or alternatively are subsequently detected using labeling agents such as antibodies (*e.g.*, labeled sheep anti-mouse antibodies where the antibody to an analyte is a murine antibody) that specifically bind to the labeling antibody.

VII. Examples

30 The following examples are offered solely for the purposes of illustration,

and are intended neither to limit nor to define the invention. In each of these examples, the term "DNA" or "plasmid" refers to the plasmid pCMV (pCMV4-CAT).

A. Materials

Transfecting agents Lipofectin and Lipofectamine were purchased from
5 Gibco/BRL (Grand Island, New York, USA). Transfectam Reagent was purchased from
Promega Corp. (Madison, Wisconsin, USA). The monocationic lipid DDAB, calcium
chloride, L-lysine (free base), poly L-lysine hydrobromide (Avg. MW 52,000), n-octyl
-D-glucopyranoside (OGP) and DNase I were obtained from Sigma Chemical Company
10 (St. Louis, Missouri, USA). TO-PRO-1 (thiazole orange monomer) was obtained from
Molecular Probes Inc., Eugene, Oregon, USA. The plasmid pCMV (GenBank accession
U02451) encoding E. coli -galactosidase (-gal), a 7.2 kb plasmid DNA reporter gene,
was obtained from Clontech Laboratories, Palo Alto, California, USA. β -gal DNA was
propagated and purified using standard techniques (Sambrook *et al.*, Molecular Cloning,
15 A Laboratory Manual, Second Ed., Cold Spring Harbor, New York (1989)). Egg
sphingomyelin (SM) and 1,2-dioleoyl-sn-Glycero-3-phosphoethanolamine (DOPE) were
purchased from Avanti Polar Lipids (Alabaster, AL). N-N-dioleoyl-N,N-
dimethylammonium chloride (DODAC) was synthesized and supplied by Steven Ansell of
INEX Pharmaceuticals Corp. (Vancouver, B.C.). TO-PRO-1 was purchased from
Molecular Probes Inc. (Eugene, OR). Dialysis membrane (SPECTRA/POR, mwco:
20 12,000-14,000) was purchased from Fisher Scientific (Ottawa, ON). All other chemicals
used were reagent grade and all solvents used were HPLC grade. Radiolabeled DNA
was used as a tracer and was generated by incorporating ^3H -dUTP into the plasmid
during bacterial growth, resulting in specific activities of $\sim 50,000$ dpm/g of DNA. All
other chemicals used in these Examples were of reagent grade and all solvents used were
25 HPLC grade. Sterile distilled water was used throughout all experiments. All materials
were used without further purification.

B. Methods

Bligh and Dyer Extraction Procedure

Non-cationic lipids, cationic lipids and DNA were solubilized in
30 chloroform:methanol:water (1:2:1:1) prior to mixing. This mixture of solvents and water
is equivalent to that used in the preparation of a Bligh and Dyer monophasic (Bligh and

Dyer, Can. J. Biochem. Physiol. 37:91-97 (1959)). Typically, DNA was added to achieve a final concentration of 10 g/mL in solution while lipid was added at various concentrations. Trace quantities of 3H-plasmid DNA were added such that 2000 to 4000 dpm were present per 10 g unlabelled DNA. The reaction mixtures were incubated at room temperature for 30 min in a total volume of 1 mL. Subsequently the Bligh and Dyer monophase was partitioned into a two phase system by the addition of water and chloroform (250 L each). The samples were mixed by vortexing and the separation of the lower organic and upper aqueous phases was facilitated by centrifugation at 2000 rpm for 5 min at room temperature. The aqueous phase was removed and retained for scintillation counting. The solvent phase was dried using a stream of nitrogen gas, and the resulting film was resuspended in SOLVABLE solubilizing agent (Dupont NEN, Boston, Massachusetts, USA) and incubated at 50° C for 1 hour. This last step was necessary to solubilize the dried DNA/lipid complex since the addition of the scintillation cocktail alone was not sufficient to dissociate the complex. PICOFLUOR scintillant (Canberra Packard, Meriden, Connecticut, USA) was added to all samples and the radioactivity (3H-DNA) was measured using a Packard TR 1900 Scintillation Counter (Canberra Packard).

Assays evaluating the stability of charge-neutralized, lipid-nucleic acid complexes were done in the presence of varying concentration of NaCl and OGP. Briefly, cationic lipid-nucleic acid complexes were prepared under conditions where 100% of the plasmid was expected to be recovered in the organic phase. NaCl or OGP was then added to the monophase system and incubations carried out at room temperature for 15 min. Bligh and Dyer extractions were performed as described above. The binding of calcium, L-lysine, and poly-L-lysine to the plasmid was evaluated using a modification of the above procedure. These nonlipid cationic materials were dissolved at various concentrations in sterile distilled water and incubated with the plasmid (10 g/mL final concentration in water) at room temperature for 30 min in a final volume of 250 L. Reaction volumes were adjusted to 1 mL with chloroform:methanol (1:2.1) to produce a monophase. Bligh and Dyer extractions were then performed as described.

Dye Intercalation Assay

The fluorochrome TO-PRO-1 was used to evaluate the state of condensation of the plasmid in the charge-neutralized lipid-nucleic acid complex. TO-PRO-1 was used in this study due to its stable intercalation into the plasmid as well

as the high sensitivity in the fluorescence detection compared with the more common intercalator ethidium bromide (see, Hirons, *et al.*, Cytometry 15:129-140 (1994)).

Plasmid was dissolved in either the Bligh and Dyer monophasic or in 100 mM OGP. Poly-L-lysine or DODAC were each added to 10 g plasmid at a 1:1 charge ratio.

5 Agarose Gel Electrophoresis

Complexes involving plasmid and poly-L-lysine were formed at a nucleic acid concentration of 10 g/mL and a 1:1 charge ratio in the presence of 100 mM OGP. Complexes involving the cationic lipid DODAC and plasmid were formed at a plasmid concentration of 10 g/mL and increasing concentrations of DODAC (10 to 320
10 nmoles/mL). The mixtures were incubated at room temperature for 30 min prior to loading onto a 0.8% agarose gel. Electrophoresis was carried out in TBE buffer according to standard techniques (Sambrook, *et al.*, Molecular Cloning: A Laboratory Manual, Second Edition, Cold Spring Harbor, New York (1989)). Nucleic acids were visualized after staining the gel with ethidium bromide (0.5 g/mL, 20 min) by
15 photography with UV transillumination.

DNase I Assay

To evaluate the protective effect of cationic lipids on DNA, the complexes formed in the presence of OGP were incubated with DNase I. Preformed charge-neutralized lipid-nucleic acid complexes (plasmid/DODAC; 1:1 charge ratio) were
20 mixed with DNase I at a concentration where plasmid alone was susceptible to degradation at 37° C for 10 min. The reactions were stopped by the addition of 25 mM EDTA and the samples were extracted using the Bligh and Dyer procedure in the presence of 150 mM NaCl. Under these conditions the charge-neutralized lipid-nucleic acid complexes dissociate and plasmid can be efficiently recovered in the aqueous
25 fraction. This DNA was precipitated with 1/10th volume of 3 M sodium acetate (pH 5.2) and 2.5 volumes of 95% EtOH and recovered by centrifugation at 14,000 g for 30 min at 4°C. The DNA pellet was resuspended in sterile distilled water and subjected to electrophoresis on a 0.8% agarose gel.

EXAMPLE 1

using either a reverse-phase method or a detergent dialysis method.

Reverse Phase Method

pCMV4-CAT plasmid was encapsulated in a lipid particle which was constructed using about 10 mg or 20 mg of lipid. The encapsulation method involved a modification of the classical reverse phase method for entrapment. Generally, 1.050 ml of chloroform: methanol in a 1:2-1 mole % ratio was added to a lipid film containing 2 μ l of 14 C-cholesteryl hexadecyl ether (6.66 μ l/ μ Ci). This was followed by the addition of 220 μ l H₂O and 33 μ l 3 H-pCMVCAT plasmid (158,000 dpm/ μ l; 1.5 mg/ml). This combination provided a clear single phase. The chloroform and most of the methanol were removed under a stream of nitrogen while vortexing. In some cases, the resulting 250 μ l suspension of encapsulated plasmid was diluted with 1 ml of H₂O and extruded 5 times through one 400 nm filter followed by extrusion 5 times through one 200 nm filter. The resulting vesicle size was approximately 150 to 200 nm in diameter. Liposome sizes before extrusion varied greatly depending on the lipid composition.

Detergent Dialysis Method

pCMVCAT was incubated with DODAC at various DODAC concentrations in 100 μ l of 1 M n-octyl-B-D-glucopyranoside and 400 μ l of H₂O for 30 min at room temperature. The resulting plasmid:DODAC mixture was added to a suspension of approximately 10 mg of lipid containing 1 μ l, 14 C-cholesteryl hexadecyl ether; 6.66 μ l / μ Ci in 100 μ l of 1M n-octyl- β -D-glucopyranoside. The suspension was dialysed against HBS at pH 7.4 overnight. The resulting encapsulated plasmid could be used without further sizing.

EXAMPLE 2

This example illustrates the level of plasmid "protection" from the external medium using anion exchange chromatography.

The extent of encapsulation or protection of the plasmid from the external medium was assessed by anion exchange chromatography as follows: a 50 μ l aliquot of each sample was eluted on a DEAE Sepharose CL-6B column and the fractions were assessed for both 3 H-plasmid and 14 C-lipid by scintillation counting. Any exposed negative charges, such as those present on DNA molecules will bind to the anion

exchange column and will not elute with the ^{14}C -lipid. DNA which has its negative charge, "protected" or non-exposed will not bind to the anion exchange resin and will elute with the ^{14}C -lipid. Alternatively, plasmid DNA was measured using the indicator dye, PicoGreen®.

5 **Reverse Phase Method**

Figure 4 presents the results describing the relationship between the amount of DODAC present in the formulation and the encapsulation efficiency for POPC:DODAC:PEG-Cer- C_{20} (20 mg total lipid) compositions after extrusion through a 400 nm filter and a 200 nm filter as measured by anion exchange chromatography. Lipid was composed of 10% PEG-Cer- C_{20} and the remaining percentage was attributable to POPC and DODAC. An increase in percent plasmid recovered was observed corresponding to an increase in DODAC concentration. No plasmid was recovered in the absence of DODAC while, at a DODAC concentration of 1.5 mole%, 90% of the plasmid was recovered after extrusion through a 200 nm filter. Nearly 100% of the plasmid recovered from extrusion through a 200 nm filter was recovered by anion exchange chromatography (Figure 5) suggesting that all of the recovered plasmid was encapsulated. This corresponded to an overall encapsulation efficiency of about 70%. Lipid recoveries after extrusion and anion exchange chromatography were 90% after extrusion through a 400 nm filter and 70% after extrusion through a 200 nm filter (see Figure 6). Of the 70% lipid recovered after extrusion through a 200 nm filter, nearly 100% was recovered after anion exchange chromatography (Figure 7). Lipid and plasmid recovery after extrusion and anion exchange chromatography were nearly identical. Table 1 illustrates the encapsulation efficiencies using several different lipid compositions. It is quite evident that a wide range of lipid compositions may be used. It is also interesting to note that PEG-Cer does not appear to be necessary in many of these lipid compositions.

Table 1. Some examples of plasmid DNA encapsulation by the modified reverse phase method. Data are shown only when at least 70% of the lipid was recovered from anion exchange chromatography.

	Reverse Phase	% encapsulation
5	Lipid composition	
	EPC-DODAC (98.9:1.1)	98%
	DOPE:EPC:DODAC (10:88.9:1.1)	24%
	DOPE:EPC:DODAC (20:78.9:1.1)	13%
	DOPE:EPC:DODAC (40:58.9:1.1)	16%
10	DOPE:EPC:DODAC-(10:85.5:4.5)	78%
	DOPE:EPC:DODAC (15:80.5:4.5)	67%
	DOPE:SM:EPC:DODAC (15:40:40:5)	53%
	DOPE:SM:EPC:DODAC (20:37.5:37.5:5)	37%
	DOPE:EPC:DODAC:PEG-Cer-C8 (25:64:1:10)	83%
15	DOPE:EPC:DODAC:PEG-Cer-C8 (50:39:1:10)	90%

Dialysis Method

Figure 8 presents the results describing the relationship between the amount of DODAC present in the formulation and the encapsulation efficiency for DOPE:DODAC:PEG-Cer-C₂₀ (84:6:10) as measured by anion exchange chromatography.

Table 2 illustrates the encapsulation efficiencies using several different lipid compositions. It is quite evident that a wide range of lipid compositions may be used. It is interesting to note that PEG-Cer appears to be necessary in these lipid compositions.

Table 2. Some examples of plasmid DNA encapsulation by the detergent dialysis method. Data are shown only when at least 70% of the lipid was recovered from anion exchange chromatography.

Detergent dialysis

Lipid composition	% encapsulation	amount of DNA	comments
DOPE:DODAC:PEG-CER-C ₁₄ (79:6:15)	64%	50 µg -400 µg/10 µmole lipid	dialyzed against 150 mM NaCl
DOPE:DODAC:PEG-CER-C ₁₄ (84:6:10)	60%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:PEG-CER-C ₂₀ (84:6:10)	52%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:EPC:PEG-CER-C ₁₄ (59:6:20:15)	20%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:DOPC:PEG-CER-C ₁₄ (74:6:10:10)	36%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:DOPC:PEG-CER-C ₁₄ (64:6:20:10)	17%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:EPC:Chol:PEG-CER-C ₁₄ (41:9:20:20:10)	57%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:EPC:Chol:PEG-CER-C ₁₄ (51:9:20:10:10)	50%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:PEG-C ₁₄ (80:10:10)	22.5%	50 µg -400 µg/10 µmole lipid	dialysed against 150 mM NaCl
DOPE:DODAC:PEG-C ₁₄ (79:11:10)	22.7%	50 µg -400 µg/10 µmole lipid	dialysed against 300 mM NaCl*
DOPE:DODAC:PEG-C ₂₀ (89.4:0.6:10)	57%	50 µg/10 µmole lipid	dialysed against 5 mM NaCl*
DOPE:DODAC:PEG-CER-C ₁₄ *87:3:10)	51%	50 µg/10 µmole lipid	dialysed against 50 mM NaCl*

* See Example 6.

EXAMPLE 3

This example illustrates the serum stability achieved using plasmid:lipid particles prepared by the methods of Example 1.

To establish the serum stability of the plasmid-lipid particles aliquots of the particle mixtures prepared according to both the reverse phase and dialysis method of

Example 1 were incubated in 80% mouse serum (Cedar Lane) for 30 min at 37° C. Prior to incubation, the lipid associated plasmid was eluted on a DEAE Sepharose CL-6B column to remove unencapsulated plasmid. Following incubation, an aliquot of the incubation mixture was eluted in HBS on a Sepharose CL-4B column.

5 As a control, 1.5 mg of free ³H-pCMVCAT was eluted on a Sepharose CL-4B column in HBS, pH 7.4 (see Figure 9A). For comparison, 1.5 mg of free ³H--pCMVCAT was incubated in 500 µl of mouse serum at 37° C for 30 min and eluted in the same manner (Figure 9B). Note that in Figure 9A, the free plasmid eluted in the void volume of the column while, in Figure 9B, the plasmid incubated in serum eluted in
10 the included volume suggesting that the plasmid had been digested by serum enzymes.

Serum stability of plasmid-lipid particles prepared by reverse phase

The stability of plasmid-lipid particles was assessed by incubation of a 50 µl aliquot in 500 µl of mouse serum (Cedar Lane) for 15 min at 37° C. A 500 µl aliquot of the incubation mixture was eluted in HBS on a Sepharose CL-4B column (Figure 10).
15 Comigration of the plasmid and lipid in the void volume strongly suggests that no plasmid degradation has occurred. Any serum-degraded plasmid or lipid should have been detected as a peak at around fraction 35 (see control results in Figure 9B).

Serum stability of plasmid-lipid particles prepared by dialysis

A 50 µl aliquot of a particle suspension was incubated in 500 µl of mouse serum at 37° C for 30 min and eluted on a Sepharose CL-4B column as described above.
20 Figure 11 shows the elution profile of the sample after incubation in serum. As can be seen in Figure 11A, 94% of the plasmid is recovered in the void volume suggesting that essentially all of the plasmid recovered from anion exchange chromatography was encapsulated.

25 To demonstrate that this experiment reflects encapsulation and not inhibition of serum nucleases by lipids in the formulation, an encapsulated plasmid DNA formulation which had not been treated by anion exchange chromatography was incubated in mouse serum for 30 min (Figure 11B). 47% of the encapsulated plasmid DNA was eluted in the included volume while 53% was eluted in the void volume of the column. The trapping efficiency as measured by anion exchange chromatography was
30 55%.

EXAMPLE 4

This example illustrates the *in vitro* resistance of the plasmid:lipid particles to DNase I digestion. Complexes formed by the addition of DOPE:DODAC (50:50) vesicles to plasmid DNA were compared to the encapsulated formulation (DOPE:DODAC:PEG-Cer-C₁₄; 84:6:10). The samples were incubated in Dnase I, amplified by PCR (Polymerase Chain Reaction) and run on an agarose gel. The DNA bands were visualized with ethidium bromide. The complexes were not stable in the DNase I (Figure 12A) in the absence of detergent (lane 9) w@e the encapsulated plasmid (Figure 12B) was stable (lane 9).

EXAMPLE 5

This example illustrates the dependence of plasmid concentration on encapsulation efficiency.

pCMVCAT plasmid was encapsulated in the lipid particles by detergent dialysis as described in Example 1. Encapsulation was approximately 50% - 60% for all concentrations tested (Figure 13). Encapsulation efficiency was independent of plasmid concentration over the range studied.

EXAMPLE 6

This example illustrates the dependence of optimal DODAC concentration for entrapment on NaCl concentration.

We found that the optimum DODAC concentration for entrapment was not only dependent on the lipid composition but also was dependent on the NaCl concentration of the dialysis buffer. pCMVCAT plasmid was encapsulated in the lipid particles by detergent dialysis as described in Example 1. Figure (14) shows the optimum DODAC concentration for encapsulation of pCMVCAT plasmid at different NaCl concentrations. Note that the amount of DODAC required in the membrane could be controlled in a predictable manner simply by changing the NaCl concentration during dialysis.

EXAMPLE 7

This example illustrates the size distribution of plasmid-lipid particles as measured by quasielastic light scattering using a Nicomp Submicron Particle Sizer (Model 370).

5 **Detergent Dialysis**

Plasmid-lipid particles were prepared by detergent dialysis as described in Example 1. The lipid composition was DOPE:DODAC:PEO-Cer-C₂₀. The particles were sized using a Nicomp Submicron Particle Sizer. Figure 15 shows the volume weighted measurement while Figure 16 shows the number weighted measurement.

10

EXAMPLE 8

This example illustrates the size distribution and structure of the plasmid-lipid particles as measured by cryoelectron microscopy.

15

Cryoelectron microscopy is a relatively nonperturbing technique which routinely has been used to study liposome shape. Liposomes are visible in the vitreous ice layer due to the relatively electron-dense phosphate head groups. The same would apply to DNA since it consists of many phosphate groups.

20

Cryoelectron microscopy was performed as described previously (Chakrabarti *et al.*, 1992; Wheeler *et al.*, 1994). Vesicles containing plasmid DNA were enriched from the formulation by differential centrifugation. A 500 μ l aliquot of the formulation was centrifuged in a microultracentrifuge for 90 min at 60,000 x g. The supernatant was decanted and the pellet was resuspended in 100 ml of HBS. A drop of the suspension was placed on a 700 mesh gold grid, blotted from behind with Whatman No. 50 filter paper to form a thin film and vitrified by plunging into liquid ethane cooled with liquid nitrogen in a Reichart Jung Universal Cryo Fixation system (Reichert Corp.). The grid was transferred to a Zeiss 10C STEM electron microscope equipped with a Gatan 126 cold stage. The stage and anticontaminator were kept at 120K and 115k, respectively, with liquid nitrogen. Regions of thin vitreous ice were observed with an acceleration voltage of 60 kV.

25

30

Figure 17A is a cryoelectron microscopy picture of an encapsulated plasmid DNA formulation. For this preparation, 400 μ g of plasmid DNA was used. The lipid composition was DOPE:DODAC:PEG-Cer-C₁₄ (84:6:10). The small arrows denote empty liposomes approximately 100 nm in diameter. These are compared to the lipid

particles containing electron-dense centers (large arrows). These electron-dense centers presumably correspond to plasmid DNA. These structures were not seen in formulations made in the absence of DNA Figure 17B.

EXAMPLE 9

5 This example illustrates the blood clearance of the plasmid:lipid particles in mice.

Reverse Phase

10 Encapsulated plasmid blood clearance was tested in three ICR mice as a function of percent recovered dose over time. Percent recovery of free ^3H -plasmid was plotted over a similar time course as a control (see Figure 18). The encapsulated plasmid exhibits a clearance rate which is much slower than that of ^3H -plasmid. Additionally, the plasmid:lipid ratio does not change significantly over the time course of the experiment confirming that the plasmid clearance rate is associated with the clearance rate of the lipid carrier itself.

15 Detergent Dialysis

20 Fusogenic particles of pCMVCAT encapsulated in DOPE:DODAC:PEG-Cer- C_{14} or DOPE:DODAC:PEG-Cer- C_{20} (84:6:10 mole%) were prepared as follows; pCMVCAT (50 μg)(42 of μl of ^3H -pCMVCAT; 108 dpm/ μl , 1.19 mg/ml) was incubated with DODAC in 100 μl of 1 M OGP and 400 μl of water for 30 min at room temperature. This DNA:DODAC complex mixture was added to a suspension of DOPE-PEG-Cer- C_{14} or DOPE:PEG-Cer- C_{20} and the particles were constructed as described in Example 1 (detergent dialysis). The plasmid:lipid particles for blood clearance studies contained 0.75 μl of ^{14}C -cholesteryl hexadecyl ether (CHE) (6.66 $\mu\text{l}/\mu\text{Ci}$) in 100 μl of 1 M OGP and 400 μl of water.

25 Clearance of pCMVCAT encapsulated in DOPE:DODAC:PEG-Cer- C_{14} and DOPE:DODAC:PEG-Cer- C_{20} (84:6:10).

 External "encapsulated" DNA was removed by anion exchange chromatography using DEAE Sepharose CL-6B prior to injection into mice. Encapsulation efficiencies were approximately 42% for the systems containing PEG-Cer-

C₂₀ and 60% for the systems containing PEG-Cer-Cer₁₄.

Three groups of three female ICR mice (20-25 g) were injected with 200 μ l of DNA-encapsulated with the plasmid:lipid particle. One group of mice was sacrificed and blood was taken at each of three time points (1, 2 and 5 hours). The plasma was separated from whole blood by centrifugation in 0.5 ml EDTA coated Tainer tubes. A 200 μ l aliquot of the plasma from each mouse was assayed for ³H-DNA and ¹⁴C-lipid by scintillation counting.

Figure 19A shows the Clearance of DNA encapsulated in a particle composed of DOPE:DODAC:PEG-Cer-C₂₀ (84:6:10). The DNA and lipid were cleared much less rapidly from the circulation than when the DOPE:DODAC:PEG-Cer-C₁₄ composition was used. Nearly 50% of the lipid and DNA are present after 2 hour. A significant amount of DNA and lipid were still present after 5 hours. The amount of DNA and lipid injected was 1.8 μ g and 853 μ g, respectively.

Figure 19B shows the clearance of DNA encapsulated in particle composed of DOPE:DODAC:PEG-Cer₁₄ (84:6: mole%). Both DNA and lipid are cleared rapidly from the circulation with only about 20% of the lipid and 10% of the DNA present in the plasma after 1 hour. The amount of DNA and lipid injected was 2.7 μ g and 912 μ g, respectively.

EXAMPLE 10

This example illustrates the *in vitro* transfection of BHK cells grown in tissue culture.

EXAMPLE 11

This example illustrates the *in vivo* transfection of tissues in mice.

***In vivo* transfection in lung, liver and spleen**

Three groups of four ICR mice were injected via tail vein with pCMVCAT encapsulated in lipid particles composed of DOPE:DODAC:PEG-Cer-C₁₄ (84:6:10) or DOPE:DODAC:PEG-Cer-C₂₀, prepared as described in Example 7. The mice were sacrificed after 2, 4 and 8 days and the lung, liver and spleen were assayed for CAT activity according to a modification of Deigh, *Anal. Biochem.*, 156:251-256 (1986). The

amount of plasmid injected was 2.6 μ g for the particles containing PEG-Cer- C_{14} and 1.5 μ g for the particles containing PEG-Cer- C_{20} .

Figure 20 shows the results of *in vivo* transfection achieved in the lung. As can be seen from this figure, treatment with DOPE:DODAC:PEG-Cer- C_{14} resulted in transfection (based on CAT activity) up to 4 days. DOPE:DODAC:PEG-Cer- C_{20} while resulting in overall lower levels of CAT activity), provided relatively constant levels of enzyme activity over 8 days.

Figure 21 shows the results of transfection achieved in the liver. For both formulations, transfection (and CAT activity) reached a maximum at 4 days.

Figure 22 shows the results of transfection achieved in the spleen wherein the maximum transfection was found for both formulations to occur after 2 days.

Examples 12-18 illustrate the formation and characterization of charge-neutralized lipid-nucleic acid intermediate complexes, in which the nucleic acid adopts hydrophobic character. In each of these examples, the term "DNA" or "plasmid" refers to the plasmid pCMV β . Examples 19 and 20 illustrate the preparation and characterization of lipid-nucleic acid particles which are suitable for transfection of cells. Examples 21-23 illustrate the serum stability and transfecting ability of these lipid-nucleic acid particles.

EXAMPLE 12

This example provides a comparison of cationic lipids and non-cationic lipids in effecting the formation of hydrophobic charge-neutralized lipid-nucleic acid complexes.

LIPOFECTIN[®] consists of sonicated unilamellar vesicles composed of DOTMA and DOPE (50:50 mole ratio, see, Felgner, *et al.*, Proc. Natl. Acad. Sci, USA 84:7413-7417 (1987)). The liposomes are prepared in water and are provided at a total lipid concentration of 1 mg/mL. DNA (10 μ g) was mixed with the liposomes in water, as described below in Example 2, to provide from 0 to 160 nmoles total lipid. Each of the mixtures was extracted using the Bligh and Dyer procedure. Surprisingly, in the presence of LIPOFECTIN[®], there was a concentration dependent reduction in DNA recovered from the aqueous phase (see Figure 23). Addition of 80 nmoles of total lipid to 10 μ g DNA resulted in greater than 95% loss of DNA from the aqueous phase. This

effect could not be achieved using liposomes prepared from egg phosphatidylcholine/DOPE (50:50 mole ratio). Thus, the hydrophobic complex which forms and is drawn into the organic phase is a result of the cationic lipid present in the complex.

5

EXAMPLE 13

This example provides a comparison of several cationic lipids in forming hydrophobic, charge-neutralized lipid-nucleic acid complexes which partition into organic solvents.

Purified monovalent cationic lipids (DOTMA, DDAB and DODAC) were each added to DNA in a Bligh and Dyer monophasic solvent system. The resulting mixtures were each partitioned into two phases by the addition of water and chloroform. Plasmid DNA levels were determined in the aqueous and organic phases as described above. The results are presented in Figure 24, and are consistent with the results presented in Figure 23. In particular, there was found to be a cationic lipid dependent loss of DNA from the aqueous phase (Figure 24A). There was no visible evidence of precipitated material at the aqueous/organic interface and quantification of the DNA in samples collected to include the interface did not account for appreciable DNA levels (results not shown). The DNA was found to be quantitatively transferred to the organic phase (Figure 24B). Additionally, greater than 95% of the DNA in the monophasic could be recovered in the organic phase when 40 nmoles monovalent cationic lipid was added. This value is identical to results presented in Figure 23 in which 80 nmoles of LIPOFECTIN® (50 mol% DOTMA) resulted in the complete loss of DNA from the aqueous phase. The results presented in Figure 24 indicate that the three different monovalent cationic lipids behave in a similar fashion under the conditions used.

EXAMPLE 14

This example illustrates the influence of multivalent cationic lipids and cationic nonlipid species on DNA partitioning into organic solvents.

LIPOFECTAMINE® (DOSPA:DOPE, 75:25 mol ratio), and TRANSFECTAM® (100% DOGS) were added to DNA (10 μ g) as preformed liposomes, as described in Example 13. The liposomes contain headgroups derived from spermine and exhibit positive charges of 5 and 4, respectively at pH < 7. As expected, significantly lower amounts of these lipids (calculated on the basis of moles) are required to mediate DNA partitioning into the organic phase (see Figure 24). Complete partitioning of the DNA into the organic phase was achieved after addition of approximately 10 nmoles DOSPA and DOGS.

Previous studies have demonstrated that DNA condenses into small toroid or rod shaped structures when the DNA phosphate charge is at least 90% neutralized (see Wilson, *et al.*, Biochemistry 18:2192-2196 (1979)). The data presented in Figure 24 was therefore expressed as a function of cation/phosphate charge ratio (Figure 25A and 25B). For comparison, results obtained after the addition of the nonlipid-based monovalent (lysine), divalent (calcium) and multivalent (poly-L-lysine) cations are included (Figures 25C and 5D). The results shown in Figure 25 demonstrate that for monovalent cationic lipids, greater than 99% of the DNA partitioned into the organic phase when a +/- charge ratio > 1 was achieved. Similar results were observed when the polyvalent lipids DOSPA and DOGS were used, although a slightly greater charge ratio was required to mediate efficient DNA transfer. However, DNA partitioning into the organic phase did not occur as a result of simple charge neutralization. When the DNA was mixed with the nonlipid cations, at charge ratios up to and in excess of 4, the majority of the DNA was invariably recovered in the aqueous phase.

EXAMPLE 15

This example illustrates that the hydrophobic, charge-neutralized lipid-nucleic acid complexes formed as described in Examples 12-14 provide the nucleic acid in an uncondensed (unprotected) configuration.

Evaluation of the hydrophobic, charge-neutralized lipid-nucleic acid complexes was carried out by assessing the ability of a small fluorescent probe to bind to

the nucleic acid in the complex. This evaluation is similar to an approach using ethidium bromide (see Gershon, *et al.*, Biochemistry 32:7143-7151 (1993)). TO-PRO-1 is a more sensitive, membrane impermeable, nucleic acid intercalating dye and therefore, provides a more stringent test of DNA binding. DNA was mixed with either a monovalent cationic lipid or poly-L-lysine in the Bligh and Dyer monophasic system (Figure 26A). TO-PRO-1 was then added to a final concentration of 1 μ M and fluorescence was measured at 533 nm (probe excitation at 509 nm). In the absence of DNA no fluorescence was observed. However, when plasmid DNA was added (10 μ g/mL) there was a >600 fold increase in fluorescence at 533 nm. When TO-PRO-1 was added to the DNA/poly-L-lysine mixture, no fluorescence was observed. This is consistent with the existence of the DNA in a condensed state due to charge neutralization. In dramatic contrast, addition of TO-PRO-1 to a hydrophobic charge-neutralized lipid-nucleic acid complex (plasmid/DODAC complex), TO-PRO-1 binding was not excluded. This result is consistent with the concept that DNA within the hydrophobic complex does not exist as a condensed structure. Figure 26B shows that similar results were obtained when TO-PRO-1 was added to plasmid DNA mixed with either poly-L-lysine or the cationic lipid DODAC in the presence of 100 mM OGP, a nonionic detergent.

EXAMPLE 16

This example illustrates the stability of the hydrophobic, charge-neutralized lipid-nucleic acid complex in detergent solutions (Figure 27) and instability in the presence of added salts (Figure 28).

Plasmid DNA (10 μ g) was mixed with 40 nmoles of DODAC in a Bligh and Dyer monophasic system as described in Example 12. OGP was added to achieve concentration up to 20 mM (20 μ moles in 1 mL) prior to separating the sample into two phases. This concentration was the maximum amount which could be added from a 2 M stock solution of OGP without disrupting the monophasic system. Regardless of the OGP concentration, greater than 99% of the DNA partitioned into the organic phase, demonstrating the stability of the hydrophobic, charge-neutralized complexes.

The effect of increasing concentrations of NaCl on the stability of the hydrophobic, charge-neutralized lipid-nucleic acid complex was also evaluated. As illustrated in Figure 28, monovalent cationic lipid binding to DNA was completely inhibited in the presence of 1 μ mole NaCl. At this level, Na⁺ is present in a 25 molar

excess relative to the amount of cationic lipid added. As expected, the complex between DNA and the polyvalent lipid DOSPA was more stable in the presence of NaCl. In fact, addition of Na⁺ in a 300-fold molar excess relative to DOSPA did not cause partitioning of the charge-neutralized lipid-nucleic acid complex into the aqueous phase.

EXAMPLE 17

This example illustrates the influence of cationic lipid binding on DNA migration by agarose gel electrophoresis.

Figure 29A shows the gel mobility characteristics of the charge-neutralized lipid-nucleic acid complexes made in the presence of OGP compared to that of the poly-L-lysine condensed DNA control. Lane 2 shows that the nonlipid-based DNA/poly-L-lysine complexes exhibit significantly reduced mobility in an agarose gel. This result is consistent with studies which have demonstrated that DNA condensed with cationic liposomes adopt a macromolecular structure that does not move within an applied electric field (see, Bertling, *et al.*, Biotechnol. Appl. Biochem. 13:390-405 (1991)). This effect may be a consequence of charge neutralization and/or increases in molecular size. In contrast, when DNA is mixed with cationic lipids under conditions of Example 12, there is no indication that the migration of DNA has been altered (see Figure 29A, lanes 3-5). These studies provide further evidence suggesting that cationic lipid binding to DNA using the methods of the present invention does not result in the condensation of DNA. Changes in DNA mobility were observed, however, when the cationic lipid concentration was increased beyond cationic lipid to DNA phosphate charge ratios of 2 (see lanes 6 to 8). For example, addition of 320 nmoles of DODAC resulted in a decrease in DNA migrating into the gel and a small proportion of the DNA migrating near the top of the gel. This indicates that condensation of DNA can be achieved with excess cationic lipids.

EXAMPLE 18

This example illustrates the ability of cationic lipids to protect plasmid DNA from enzymatic digestion.

To determine the ability of cationic lipids to protect plasmid DNA from enzymatic digestion, DNase I mediated degradation of the lipid-nucleic acid complex (plasmid/DODAC complex prepared as described above) was also evaluated using agarose gel electrophoresis (see Figure 29B). In these experiments, plasmid in OGP solution was mixed with a sufficient amount of DNase I to generate small DNA fragments after a 10 min incubation at 37°C (lane 2). Lane 1 shows undigested plasmid as a control. Using identical conditions, the complexes (plasmid complexed with the monocationic lipid DODAC) was not protected against the enzymatic activity of DNase I (lane 4). DNA extracted from the complex in the absence of DNase I (lane 3) shows intact DNA. This provides further evidence that the nucleic acids in the lipid-nucleic acid complexes is in an uncondensed state and is susceptible to degradation.

EXAMPLE 19

This example illustrates the preparation of lipid-nucleic acid particles of β -gal, DODAC and ESM.

Cationic lipid DODAC, non-cationic lipid ESM, and nucleic acid β -gal plasmid were formulated using a detergent dialysis method according to the "strategy of reverse order" (see Figure 30) as follows:

Individual solutions of DNA (10 μ g in 200 μ L of 200 mM aqueous OGP), DODAC (160 nmoles in 400 μ L OGP) and ESM (160 nmoles in 400 μ L OGP) were prepared. The ESM and DODAC solutions were each sonicated at low power at 10-20 pulses. The DNA solution was then added to the ESM solution and the mixture was allowed to incubate for 0.5 hr at room temperature. The DODAC solution was added slowly to the DNA/ESM mixture while vortexing the mixture at low speed. The resultant mixture (1 mL) was placed in a SPECTRA/POR, mwco: 12-14,000 dialysis tube (Fisher Scientific) and dialyzed against six changes of 2 L of distilled sterile water over 36 hours. Size distribution of the complexes formed was determined using quasielastic light scattering (QELS) technique (Nicom 370 particle sizer operating at a wavelength of 632.8 nm). Figure 31 shows that two populations of particles were

observed, one group sized from 50 to 150 nm and the second sized 500 to 1000 nm. The relative numbers of each depended on the type of non-cationic lipid(s) used, the amount and concentration of the two lipid components, and the DNA/lipid ratio. About 20-40% of the relative volume of the mixture were the smaller sized complexes which accounted for over 90% of the total particle number.

EXAMPLE 20

This example illustrates the state of condensation of the DNA in the lipid-nucleic acid particle.

The fluorochrome (TO-PRO-1) was used to evaluate the state of condensation of the DNA in the lipid-nucleic acid particle. A 200 μ L aliquot of the lipid-nucleic acid particle (containing 2 μ g plasmid DNA prepared with the protocol given in Example 19) was diluted to 1 mL with 100 mM OGP. TO-PRO-1 was added to make a final concentration of 1 μ M. To measure fluorescence, spectrofluorometric measurements were performed using a Luminescence Spectrometer 50B (Perkin Elmer Ltd., Buckinghamshire, England) with an excitation wavelength of 509 nm and an emission wavelength of 533 nm. The results are presented in Figure 32 in which the values are expressed as arbitrary fluorescence units. As Figure 32 illustrates, plasmid DNA in lipid-nucleic acid complexes containing DODAC/ESM is condensed or protected by the lipid component. Moreover, the detergent (OGP) can dissolve the complex to uncondense the DNA (see Figure 32).

DNA in lipid-nucleic acid particles containing DODAC/DOPE is partially accessible to TO-PRO-1 at a lipid/DNA charge ratio (+/-) of 4:1, however, at 8:1 DNA is completely protected by the lipid component. This result suggests that the nucleic acid (DNA) is partially condensed at the lower charge ratio and fully condensed at the higher ratio (Figure 32).

EXAMPLE 21

This example demonstrates the stability of lipid-nucleic acid particles in phosphate-buffered saline and in serum containing media.

A lipid-nucleic acid particle formulation was prepared according to the procedure described in Example 19. Portions of the formulation (using either ESM or

DOPE as the neutral lipid) were combined with PBS (140 mM NaCl, 10 mM Na₂HPO₄) or serum-containing medium and incubated for two hours at 37°C. The resulting complexes were isolated and examined for any changes in QELS size results or transfection efficiency. No difference was found for any of the formulations, indicating that the complexes were not disrupted by either sodium or serum components. One portion which was incubated with PBS for 10 days still showed very good transfection efficiency.

EXAMPLE 22

This example illustrates the protection of DNA against DNase I which is afforded by the lipid-nucleic acid particles.

A lipid-nucleic acid particle formulation of 10 µg DNA, 160 nmoles DODAC and 160 nmoles ESM in 1 mL total volume was prepared according to the method described in Example 19. The susceptibility of the DNA in this formulation to degradation by DNase I was evaluated by mixing the formulation with DNase I in the presence of OGP (1:1 charge ratio). The level of DNase I was equivalent to that which degrades uncomplexed DNA within 10 minutes at 37°C. The reactions were stopped after 10 min by the addition of 25 mM EDTA. DNA was extracted using the Bligh and Dyer extraction procedure in the presence of 150 mM NaCl. Under these conditions the cationic lipid/DNA complex dissociates and the resulting DNA can be efficiently recovered from the aqueous fraction. This DNA was precipitated with 1/10th volume of 3M sodium acetate (pH 5.2) and 2.5 volumes of 95% ethanol and recovered by centrifugation at 14,000 g for 30 min at 4°C. The DNA pellet was resuspended in sterile distilled water and subjected to electrophoresis on a 0.8% agarose gel (Gibco, BRL). The results are shown in Figure 33. As Figure 33 indicates, complexes containing ESM provide protection of DNA from DNase I degradation.

EXAMPLE 23

This example illustrates the *in vitro* transfection of CHO or B16 cell lines using lipid-nucleic acid particles prepared by the method of Example 19.

In vitro transfection was performed using a 96-well cell culture plate (Costar, Cambridge, Massachusetts, USA) containing 50% confluent growth of either Chinese Hamster Ovary (CHO) or murine melanoma (B16) cell lines. Appropriate amounts (about 6-50 μ L) of the lipid-nucleic acid particle formulation (10 μ g DNA/mL) were premixed with medium containing 10% serum to a final volume of 150 μ L. The medium surrounding the cells was removed using a needle syringe and replaced with the lipid-nucleic acid particles in 10% serum-containing medium. The cells and complex were incubated for a further 48 hours at 37°C. The transfection efficiency was evaluated using β -gal stain or an enzyme activity assay. Results are presented in Figure 34.

The transfection study showed excellent transfection efficiency with ESM-containing complexes and with DOPE-containing complexes (not shown). A cationic lipid to DNA charge ratio of 3:1 to 4:1 gave the best *in vitro* transfection results.

EXAMPLE 24

This example illustrates the properties of nucleic acid-lipid particles prepared as described below in the presence of 100 mM (A) or 20 mM (B) *n*-octyl β -D-glucopyranoside (OGP).

The protocol involves the preparation of solutions of pCMV β DNA in OGP and lipid-detergent mixed micelles. DODAC and the neutral lipid were dissolved in the same concentration of OGP used to dilute the DNA solution. To ensure that the lipids were completely dissolved, the mixtures were heated to 50° C for 5 min and vortexed vigorously. Individual solutions were prepared with or without neutral lipid. When there was no neutral lipid involved, the DNA was added to the DODAC solution followed by gentle vortexing and then incubated at room temperature for 30 min. When the neutral lipid was present, the detergent solution containing DNA was mixed with the detergent solution containing the neutral lipid. This mixture was incubated for 30 min at room, temperature and then added to detergent solution containing the cationic lipid

DODAC. To remove detergent mixtures were transferred to dialysis bags and dialyzed against six changes of sterile water over 72 hrs. The volume of each sample was less than 1 mL.

nucleic acid-lipid particle formation was evaluated by measuring changes in 90° light scattering intensity at 600 nm (slit width of 2.5 nm). This wavelength was used because light scattering from detergent micelles alone was negligible, therefore, the formation of nucleic acid-lipid particles could be monitored. This technique was also used to assess the ability of OGP to solubilize preformed liposomes of DODAC or SM. Multilamellar liposomes were prepared at a final lipid concentration of 1.0 mM by hydrating powdered lipid in distilled water at 60°C. The lipid suspensions were sonicated for 5 min (100 watts, 90% duty cycle, at 20 kHz) using a probe sonicator (Sonilier Cell Disrupter 350, Branson Sonic Power Co., Danbury, CN) to produce homogeneous suspension. For the lipid dissolution measurement, an aliquot of the lipid suspension was diluted with distilled water to a final lipid concentration of 0.2-1.0 mM. This lipid suspension was titrated with 200 mM OGP and mixed well by pipetting. Light scattering intensity was measured at room temperature using a Luminescence Spectrometer 50B (Perkin Elmer).

In 100 mM OGP there were no significant changes in solution turbidity observed when DNA was added to DODAC/OGP mixed micelle solution in the presence and absence of SM. After 3 hrs of dialysis the solutions became turbid and light scattering increased, a reflection of increased particle size and/or aggregation. After 4.5 hrs., a decrease in light scattering was observed for systems prepared in the absence of SM, a result of the formation of larger visible aggregates. When the samples were prepared in 20 mM OGP (Figure 35B), a concentration close to the critical micelle concentration of OGP in the absence of added lipids, light scattering increased at the time when DNA was added to DODAC/OGP micelles. This increase in turbidity is indicative of spontaneous particle formation spheroidal mixed micelles. It is therefore unlikely that lipid vesicles form under conditions where the detergent concentration is equal or greater than 20 mM. nucleic acid-lipid particle formation in the presence of 20 mM OGP is likely not due to DNA-mediated aggregation of cationic liposomes. We believe that nucleic acid-lipid particle formation is the result of the hydrophobic lipid-DNA complex adopting a structure that minimizes lipid acyl chain contact with water.

The physical characteristics of the nucleic acid-lipid particles, formed either spontaneously or following detergent removal, are summarized in Table 3 and Figure 37.

The parameters evaluated include (i) particle size as estimated by QELS and electron microscopy, (ii) the observed degree of aggregation/ flocculation, and (iii) an assessment of TO-PRO-1 binding, an intercalating agent that fluoresces when bound to DNA.

Since it is believed that nucleic acid-lipid particle formation is dependent on cationic lipid binding to DNA, particle characteristics were assessed under conditions where the cationic lipid to anionic phosphate charge ratio was varied from 1:1 to 8:1. Under conditions where particle formation occurred following detergent removal (*i.e.* lipid and DNA mixtures prepared in 100 mM OGP) the resulting particles were large (>2000 nm) and aggregated (Table 3). This tendency to aggregate was dependent on the charge ratio.

After nucleic acid-lipid particle formation, the DNA assumed a structure that was not accessible to TO-PRO-1 intercalation, suggesting that the DNA was condensed. It should be noted that a condensation index of ≈ 1.0 is equivalent to that obtained when DNA is condensed by the addition of polylysine (Reimer *et al.*, 1995).

When low detergent concentrations (20 mM OGP) were used to promote spontaneous nucleic acid-lipid particle formation there was no significant change in particle size or aggregation state as a function of detergent removal, except at charge ratios of 1:1 and 1.5:1 (Table 32), where significant increases in particle size were observed.

As shown in Figure 37A, QELS data indicated that for samples prepared using the 2:1 charge ratio, the particles were homogeneous and fit a Gaussian analysis with a mean diameter of 59 ± 38 nm.

This result is comparable with observations made using negative stain electron microscopy (Figure 37B). nucleic acid-lipid particles were evaluated by electron microscopy (EM) using two methods. First, the samples were prepared for negative stain EM by placing a drop of a concentrated nucleic acid-lipid particle formulation (3 mM lipid) onto a formvar coated nickel grid. After 1 min the sample was carefully drawn away using filter paper and stained with a 2.5% ammonium molybdate solution. The stained samples were immediately examined and photographed using a Carl Zeiss EM10CR electron microscope operated at 80 Kv. Second, nucleic acid-lipid particles were prepared for freeze-fracture EM, where a sample of concentrated nucleic acid-lipid particle formulation (15 mM lipid) was mixed with glycerol (25% v/v), frozen in a freon slush, and subjected to freeze-fracture employing a Balzers BAF 400D apparatus. Micrographs were obtained using a JEOL Model JEM- 1200EX electron microscope.

Data obtained from freeze-fracture electron microscopic analysis of the particles (Figure 37C) indicated that, regardless of sample concentration (up to 15 mM total lipid), there were only a few regions on the freeze-fracture replica that exhibited fracture surfaces typical of membrane bilayer structures. Instead, numerous bumps were detected on the replica. This is consistent with the suggestion that particles rather than liposomes were formed using the procedures described here.

DNA was accessible to TO-PRO-1 following spontaneous particle formation and condensation indices of less than 0.05 were typically measured prior to detergent removal. This result was unexpected and suggests that particle formation is not a indicator of whether DNA is condensed. After detergent removal, TO-PRO-1 intercalation was not observed and the resulting DNA condensation indices were high (≈ 1.0) (Table 3).

Table 3. Characteristics of lipid-DNA particles formed with pCMV β /DODAC/SM prepared using 20 mM and 100 mM OGP before and after dialysis.

		mean diameter \pm SD(nm) ^b		aggregation state ^c	condensation index ^d
	(cation/anion ₁)	before dialysis	after dialysis		
5	100 mM OGP				
	1:1	ND*	>2000	++	0.759
	2:1	ND	>2000	+	0.927
10	4:1	ND	>2000	+	0.974
	8:1	ND	>2000	++	0.991
	20 mM OGP				
	1:1	71.2 \pm 37.0	192 \pm 110	-	0.875
	1.5:1	63.1 \pm 33.8	119 \pm 76	--	0.985
15	2:1	60.8 \pm 33.3	58.6 \pm 37.8	--	0.991
	4:1	56.7 \pm 32.0	55.9 \pm 32.6	--	0.994
	8:1	64.6 \pm 33.4	66.4 \pm 35.4	--	0.989

* The charge ratio of cationic lipids to DNA phosphate groups.

^b Mean diameter was measured using QELS techniques as described in the Methods. The instrument used to evaluate particle size is accurate only under conditions where the mean particle size is less than 1.0 μ m. The aggregation state of the formulations after dialysis was evaluated qualitatively through visual inspection of the samples and scored as follows: ++ large aggregates that settle out of solution within 5 min after sample mixing; + small to medium aggregates present but the solution retains a uniform "milky" appearance; - no obvious aggregates unless viewed by microscopy; -- no aggregates and homogeneous as assessed by QELS.

^d DNA condensation index, a reflection of TO-PRO-1 binding to DNA in the presence and absence of lipid binding, was determined as described in the Methods.

* NID: not detectable because particles were not formed.

DNA Stability Assay

To evaluate the protective effect of lipids on DNA, 100 μ l of the formulations containing 1 μ g pCMV β DNA were incubated with 0.67 unit of DNase I at 37°C for 20 min in the presence of buffer (0.05 M Tris-HCl pH 8.0, 0.01 M MgSO₄, 0.1 mM dithiothreitol) or 20 mM OGP. The enzymatic reactions were stopped by the addition of 5 μ l of 0.5M EDTA and 3 μ l of 5M NaCl. DNA was extracted using a modified Bligh and Dyer extraction procedure (Reimer *et al.*, 1995). Under these conditions, lipid and DNA dissociated and the resulting DNA was efficiently recovered in the aqueous phase. DNA was precipitated with one-tenth volume of sodium acetate (pH 5.2) and 2.5 volumes of 95% ethanol at -20°C for 30 min and recovered by centrifugation at 12,000 x g for 30 min at 4°C in a microcentrifuge (Eppendorf). The

DNA pellet was resuspended in 10 μ l sterile distilled water and subjected to electrophoresis on a 0.8% agarose gel in TBE buffer (89 mM Tris-Borate, 2 mM EDTA, pH 8.0).

To further define the characteristics of the nucleic acid-lipid particles produced as a consequence of DNA-cationic lipid complex formation, we evaluated whether the DNA in the nucleic acid-lipid particles was protected against the endonuclease activity of DNase I. This is an important characteristic since we are developing these systems for *in vitro* and *in vivo* DNA transfer. The results presented in Figure 38A show that after detergent removal, DNA within the particle remained intact in the presence of DNase I (lanes 5 and 7). Interestingly, DNA within particles that had formed spontaneously in the presence of 20 mM OGP remained intact in the presence of DNase I even in the absence of detergent removal (Figure 38B, lane 5).

EXAMPLE 25

This example illustrates that the nucleic acid-lipid particles prepared as described in Example 24 are useful as plasmid delivery systems *in vitro*.

CHO cells (American Type Tissue Culture, Rockville, MD) were plated at 2×10^4 cells per well in a 96 well culture plate (Costar, Cambridge, MA) in α MEM supplemented with 5% Fetal Bovine Serum (FBS). The cells were grown for 24 hrs in a 37°C 5% CO₂ incubator and were 40-50% confluent at the time of transfection. Media was removed from cells prior to addition of 100 μ l of diluted nucleic acid-lipid particle formulations prepared from 25 μ l nucleic acid-lipid particles formulation containing 0.3-1.2 μ g DNA and 75 μ l of α MEM supplemented with 10% FBS. Cells were incubated at 37°C for 4 hrs, prior to the addition of 100 μ l of α MEM (10% FBS) containing 100 μ g/mL gentamicin sulphate. The cells were further incubated at 37°C for two days and then assayed for β -galactosidase activity. Media was removed from each well and 30 μ l of a cell lysis buffer (0.1% Triton X-100, 250 mM Na₂HPO₄, pH 8.0) was added. Subsequently, 50 μ l of bovine serum albumin (0.5% in phosphate buffer, pH 8.0) was added to each well followed by the addition of 150 μ l of chlorophenol red galactopyranoside (CPRG, 1 mg/mL in 60 mM Na₂HPO₄, 1 mM MgSO₄, 10 mM KCl, 50 mM β -mercaptoethanol). Absorbance at 590 nm was read on a Titertek Multiscan Type 310C microtiter plate reader (Flow Laboratories, Mississauga, ONT) at various times and the resulting optical densities were converted to mU β -galactosidase using a

standard curve obtained for each plate. All assays were evaluated in at least 3 wells per plate and the values are reported as means \pm standard deviations.

Chinese Hamster Ovary (CHO) cell transfection studies using nucleic acid-lipid particles prepared using 100 mM OGP are presented in figure 39 and are evaluated by enzyme production (β -galactosidase activity) as the end product of gene transfer. Only those systems that were >2000 nm were effective at transfecting cells. The transfection efficiency for these systems increased as the cationic lipid to DNA nucleotide phosphate (charge) ratio increased from 1:1 to 4:1 (Figure 39A). Unlike results with preformed liposome-DNA aggregates (see, *e.g.*, Jarnagin *et al.*, 1992); however, transfection was not affected by the presence of serum.

Particle-induced cell toxicity data are shown in Figure 39B as a reduction in enzyme activity/well with increasing amounts of nucleic acid-lipid particle formulation.

A significant difference between preformed liposome-DNA aggregates and the nucleic acid-lipid particles concerns the use of DOPE as a helper lipid required for optimal transfection (Felgner & Ringold, 1989; Smith *et al.*, 1993; Farhood *et al.*, 1995). As shown in Figure 39C, large particles prepared using the detergent dialysis procedure with DODAC and SM were more effective in transfecting CHO cells *in vitro* than particles prepared using DODAC and DOPE.

EXAMPLE 26

This example illustrates the encapsulation of plasmid DNA in a lipid vesicles by the detergent dialysis method using different cationic lipids. The dialysis method is as described previously for DODAC (EXAMPLE 1). The amount of plasmid entrapped with different mol % of the various cationic lipids was determined by DEAE Sepharose chromatography (described in EXAMPLE 2). The entrapment efficiency was similar for all cationic lipids tested with approximately 50 to 60% of plasmid DNA. The cationic lipid concentration required in the formulation for optimal plasmid encapsulation was 6.5 % for DOTMA, DSDAC and DODMA-AN in Figure 41(a); 8% DODAC and DMRIE in 41(b); DCchol in 41(c).

EXAMPLE 27

This example demonstrates the stability of plasmid containing vesicles

prepared with different cationic lipids. The serum stability and protection of the plasmid from serum nucleases was determined by the method described in EXAMPLE 3.

Stability and protection was similar for all preparations obtained with the different cationic lipids. As examples the elution profile for preparations containing DODAC Figure 42(a); DOTMA, Figure 42(b), and DSDAC, Figure 42(c) are given after incubation in mouse serum for 30 min at 37° C.

EXAMPLE 28

This example demonstrates the encapsulation of plasmid DNA with the ionizable lipid AL-1 ($pK_a = 6.6$) by the dialysis method (as described in EXAMPLE 1). AL-1 is positively charged at acidic pH and neutral at $pH > 7$. Different concentrations of AL-1 were used in the lipid formulations at pH 4.8 and 7.5 respectively. The amount of encapsulated DNA was determined using the PicoGreen assay. Non-encapsulated DNA was removed first by anion exchange chromatography and the entrapped DNA determined with PicoGreen after solubilization of the lipid vesicles in detergent.

Encapsulation of plasmid DNA using DODAC is shown as comparison. At pH 4.8 maximal encapsulation of approximately 75% of plasmid DNA was achieved with 8% AL-1 similar to the DODAC formulation at pH 7.5. However, no DNA entrapment was obtained with AL-1 at pH 7.5. Figure 43. This clearly demonstrates the requirement of positively charged lipids for DNA entrapment.

EXAMPLE 29

This example shows the stability of the plasmid containing vesicles formed with AL-1 at pH 4.8 and the protection of the entrapped DNA from degradation by serum nucleases at pH 7.5. 3H -DNA and ^{14}C -CHE (cholesteryl hexadecyl ether) were used to follow the DNA and lipid respectively. The vesicles formed with AL-1 at pH 4.8 were incubated in mouse serum for 1.5 hr at 37° C at pH 7.5. The non-encapsulated DNA was not removed in the preparations used for serum incubation. After incubation in serum the vesicles were separated on a Sepharose CL6B column. Lipid and DNA were detected by radioactivity in the different fractions. Figure 44. Approximately 60% of the DNA was protected from serum nucleases. When vesicles formed with AL-1 at pH 7.5 were incubated in serum virtually all the DNA was degraded and eluted as

fragments separated from lipids. Figure 45.

EXAMPLE 30

Example 30 demonstrates the effect of the PEG-ceramide concentration on the encapsulation efficiency by the dialysis method with 7.5 % DODAC and DOPE. The non entrapped DNA in the various formulations with different PEG-C14 concentrations was separated by DEAE Sepharose CL6B chromatography. DNA and lipid recovered are shown as a function of %PEG-C14. Best entrapment was obtained with 10 mol% PEG-C14. Figure 46. However, a more recent experiment showed optimum entrapment in the range of 10 to 15 mol% (data not shown).

VII. Conclusion

As discussed above, the present invention comprises novel lipid-nucleic acid complexes and methods of making them. In a number of embodiments, hydrophobic DNA intermediates can be isolated and the DNA exists in a non-condensed form as measured by dye binding and DNase I sensitivity. These complexes can be used in the preparation of other lipid-nucleic acid particles.

In further embodiments, the invention provides methods for preparing serum-stable nucleic acid-lipid particles which are useful for the transfection of cells, both *in vitro* and *in vivo*.

The methods described for the preparation and uses of the various nucleic acid particles can be used with essentially any nucleic acid which can exist in a lipophilic state when complexed with an appropriate cationic lipid. Examples of some constructs include those encoding adenosine deaminase, the low density lipoprotein receptor for familial hypercholesterolemia, the CFTR gene for cystic fibrosis, galactocerebrosidase for Gaucher's disease, and dystrophin or utrophin into muscle cells for Duchenne's muscular dystrophy.

All publications, patents and patent applications mentioned in this specification are herein incorporated by reference into the specification for all purposes to the same extent as if each individual publication, patent or patent application was specifically and individually indicated to be incorporated herein by reference.

Although the foregoing invention has been described in some detail by way

of illustration and example for purposes of clarity of understanding, it will be obvious that certain changes and modifications may be practiced within the scope of the appended claims.

WHAT IS CLAIMED IS:

1. A hydrophobic lipid-nucleic acid complex consisting essentially of cationic lipids and nucleic acids, said complex being charge-neutralized and soluble in organic solvents.
2. A complex in accordance with claim 1, wherein said nucleic acid is a plasmid.
3. A complex in accordance with claim 1, wherein said cationic lipids are members selected from the group consisting of DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS and combinations thereof.
4. A method for the preparation of lipid-nucleic acid particles, comprising:
 - (a) contacting nucleic acids with a solution comprising non-cationic lipids and a detergent to form a nucleic acid-lipid mixture;
 - (b) contacting cationic lipids with said nucleic acid-lipid mixture to neutralize the negative charge of said nucleic acids and form a charge-neutralized mixture comprising detergent, nucleic acids and lipids; and
 - (c) removing said detergent from said charge-neutralized mixture to provide said lipid-nucleic acid particles in which said nucleic acids are protected from degradation.
5. A method in accordance with claim 4, wherein said solution of step (a) further comprises an organic solvent.
6. A method in accordance with claim 4, wherein said cationic lipids are members selected from the group consisting of DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS and combinations thereof.
7. A method in accordance with claim 4, wherein said non-cationic lipids are selected from the group consisting of ESM, DOPE, polyethylene glycol-based polymers and combinations thereof.
8. A method in accordance with claim 4, wherein said detergent is octyl- β -D-

glucopyranoside, said cationic lipid is DODAC, said non-cationic lipid is ESM, and said detergent is removed by dialysis.

9. A method in accordance with claim 8, wherein said non-cationic lipids are combinations of ESM and PEG-Ceramide.

10. A method for introducing a nucleic acid into a cell, comprising:

- (a) preparing a lipid-nucleic acid particle according to the method of claim 4; and
- (b) contacting said cell with said lipid-nucleic acid particle for a period of time sufficient to introduce said nucleic acid into said cell.

11. A method in accordance with claim 11, wherein said lipid-nucleic acid particle comprises a plasmid, DODAC and ESM.

12. A method for the preparation of lipid-nucleic acid particles, comprising:

- (a) contacting an amount of cationic lipids with nucleic acids in a solution; said solution comprising of from about 15-35% water and about 65-85% organic solvent and said amount of cationic lipids being sufficient to produce a +/- charge ratio of from about 0.85 to about 2.0, to provide a hydrophobic, charge-neutralized lipid-nucleic acid complex;
- (b) contacting said hydrophobic lipid-nucleic acid complex in solution with non-cationic lipids, to provide a lipid-nucleic acid mixture; and
- (c) removing said organic solvents from said mixture to provide said lipid-nucleic acid particles in which said nucleic acids are protected from degradation.

13. A method in accordance with claim 12, wherein said cationic lipids are members selected from the group consisting of DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS and combinations thereof.

14. A method in accordance with claim 12, wherein said non-cationic lipids are members selected from the group consisting of ESM, DOPE, polyethylene glycol-based polymers and combinations thereof.

15. A method in accordance with claim 12, wherein said organic solvents are members selected from the group consisting of methanol, chloroform, methylene chloride, ethanol, diethyl ether and combinations thereof.

16. A method in accordance with claim 12, wherein said nucleic acid is a plasmid, said cationic lipid is a member selected from the group consisting of DODAC, DDAB, DOTMA, DOSPA, DMRIE, DOGS and combinations thereof, said non-cationic lipid is a member selected from the group consisting of ESM, DOPE, polyethylene glycol-based polymers and combinations thereof, and said organic solvent is a member selected from the group consisting of methanol, chloroform, methylene chloride, ethanol, diethyl ether and combinations thereof.

17. A method for introducing a nucleic acid into a cell, comprising;

- (a) preparing a lipid-nucleic acid particle according to the method of claim 13;

and

- (b) contacting said cell with said lipid-nucleic acid particle for a period of time sufficient to introduce said nucleic acid into said cell.

18. A lipid-nucleic acid particle prepared according to claim 4.

19. A lipid-nucleic acid particle prepared according to claim 12.

20. A method for the preparation of serum-stable plasmid-lipid particles, comprising:

- (a) combining a plasmid with cationic lipids in a detergent solution to provide a coated plasmid-lipid complex;
- (b) contacting non-cationic lipids with said coated plasmid-lipid complex to provide a solution comprising detergent, a plasmid-lipid complex and non-cationic lipids; and
- (c) removing said detergent from said solution of step (b) to provide a solution of serum-stable plasmid-lipid particles, wherein said plasmid is encapsulated in a lipid bilayer and said particles are serum-stable and have a size of from about 50 to about 150 nm.

21. A method in accordance with claim 20, wherein said removing is by dialysis.

22. A method in accordance with claim 20, wherein step (b) further comprises adding a polyethylene glycol-lipid conjugate.

23. A method in accordance with claim 22, wherein said polyethylene glycol-lipid conjugate is a PEG-ceramide conjugate.

24. A method in accordance with claim 20, further comprising;
(d) sizing said particles to achieve a uniform particle size.

25. A method in accordance with claim 20, wherein said cationic lipids are selected from the group consisting of DODAC, DDAB, DOTAP, DOTMA, DOSPA, DOGS, DC-Chol and combinations thereof.

26. A method in accordance with claim 20, wherein said non-cationic lipids are selected from the group consisting of DOPE, POPC, EPC and combinations thereof.

27. A method in accordance with claim 20, wherein said detergent solution comprises a detergent having a critical micelle concentration of between about 20 mM and 50 mM.

28. A method in accordance with claim 8, wherein said detergent is n-octyl- β -D-glucopyranoside.

29. A method for the preparation of serum-stable plasmid-lipid particles, comprising;

- (a) preparing a mixture comprising cationic lipids and non-cationic lipids in an organic solvent;
- (b) contacting an aqueous solution of plasmid with said mixture prepared in step (a) to provide a clear single phase; and
- (c) removing said organic solvent to provide a suspension of plasmid-lipid particles, wherein said plasmid is encapsulated in a lipid bilayer, and said

particles are stable in serum and have a size of from about 50 to about 150 nm.

30. A method in accordance with claim 29, wherein said non-cationic lipids comprise a polyethylene glycol-lipid conjugate.

31. A method in accordance with claim 30, wherein said polyethylene glycol-lipid conjugate is a PEG-ceramide conjugate.

32. A method in accordance with claim 29, wherein said cationic lipids are selected from the group consisting of DODAC, DDAB, DOTAP, DOTMA, DOSPA, DOGS, DC-Chol and combinations thereof.

33. A method in accordance with claim 29, wherein said non-cationic lipids are selected from the group consisting of DOPE, POPC, EPC and combinations thereof.

34. A plasmid-lipid particle prepared according to claim 20.

35. A method for introducing a plasmid into a cell, comprising;
(a) preparing a plasmid-lipid particle according to the method of claim 20; and
(b) contacting said cell with said plasmid-lipid particle for a period of time sufficient to introduce said plasmid into said cell.

36. A method in accordance with claim 35, wherein said plasmid-lipid particle comprises a plasmid, DODAC, POPC and a PEG-Ceramide selected from the group consisting of PEG-Cer-C₂₀ and PEG-Cer-C₁₄.

37. A method in accordance with claim 35, wherein said plasmid-lipid particle comprises a plasmid, DODAC, DOPE and a PEG-Ceramide selected from the group consisting of PEG-Cer-C₂₀ and PEG-Cer-C₁₄.

38. A plasmid-lipid particle prepared according to claim 29.

39. A method for introducing a plasmid into a cell, comprising;

- (a) preparing a plasmid-lipid particle according to the method of claim 29; and
- (b) contacting said cell with said plasmid-lipid particle for a period of time sufficient to introduce said plasmid into said cell.

40. A method in accordance with claim 39, wherein said plasmid-lipid particle comprises a plasmid, DODAC, POPC and a PEG-Ceramide selected from the group consisting of PEG-Cer-C₂₀ and PEG-Cer-C₁₄.

41. A method in accordance with claim 39, wherein said plasmid-lipid particle comprises a plasmid, DODAC, DOPE and a PEG-Ceramide selected from the group consisting of PEG-Cer-C₂₀ and PEG-Cer-C₁₄.

1/35




FIG. 1.

2/35




FIG. 2.

3/35






FIG. 3.

SUBSTITUTE SHEET (RULE 26)

**FIG. 4.****FIG. 5.**




FIG. 7.




FIG. 6.




FIG. 8.




FIG. 10.

7/35




FIG. 9A.




FIG. 9B.

8/35




FIG. IIA.




FIG. IIB.

9/35




FIG. 12A.




FIG. 12B.




FIG. 13.




FIG. 14.

11/35




FIG. 15.




FIG. 16.

12/35




FIG. 17A.




FIG. 17B.

13/35




FIG. 18.




FIG. 20.

14/35




FIG. 19A.




FIG. 19B.




FIG. 21.







FIG. 22.

**FIG. 23.****FIG. 24A.****FIG. 24B.**

17/35




FIG. 25A.




FIG. 25B.




FIG. 25C.




FIG. 25D.

18/35




FIG. 26A.




FIG. 26B.

19/35




FIG. 27.




FIG. 28.




FIG. 29A.




FIG. 29B.

21/ 35




FIG. 30.

22/35




FIG. 3IA.





FIG. 3IB.

23/35

*FIG. 32.*




FIG. 33.

25/35




FIG. 34.

26/35




FIG. 35A.




FIG. 35B.

27/35




FIG. 36.




FIG. 37A.




FIG. 38A.




FIG. 38B.

Figure 37B








Figure 37C



30/35

**FIG. 39A.****FIG. 39B.****FIG. 39C.**

31/35




FIG. 40.

32/35




FIG. 4IA.




FIG. 4IB.




FIG. 4IC.

33/35




FIG. 42A.




FIG. 42B.




FIG. 42C.

34/35




FIG. 43.




FIG. 44.

35/35




FIG. 45.




FIG. 46.

2/35




FIG. 2.

3/35




FIG. 3.

SUBSTITUTE SHEET (RULE 26)




FIG. 4.




FIG. 5.




FIG. 7.




FIG. 6.




FIG. 8.




FIG. 10.

7/35




FIG. 9A.




FIG. 9B.

8/35




FIG. IIA.




FIG. IIB.

9/35




FIG. 12A.




FIG. 12B.




FIG. 13.




FIG. 14.

11/35




FIG. 15.




FIG. 16.

12/35




FIG. 17A.




FIG. 17B.




FIG. 18.




FIG. 20.

M/35




FIG. 19A.




FIG. 19B.




FIG. 21.




FIG. 22.




FIG. 23.




FIG. 24A.




FIG. 24B.

17/35




FIG. 25A.




FIG. 25B.




FIG. 25C.




FIG. 25D.

18/35




FIG. 26A.




FIG. 26B.

19/35




FIG. 27.





FIG. 28.

*FIG. 29A.**FIG. 29B.*

21/35




FIG. 30.

22/35




FIG. 31A.





FIG. 31B.

23/35

*FIG. 32.*




FIG. 33.

25/35




FIG. 34.

26/35




FIG. 35A.




FIG. 35B.

27/35




FIG. 36.




FIG. 37A.



*FIG. 38A.**FIG. 38B.*




Figure 37B




Figure 37C



30/35

**FIG 39A.****FIG. 39B.****FIG. 39C.**

31/35

**FIG. 40.**

32/35




FIG. 41A.




FIG. 41B.




FIG. 41C.

33/35




FIG. 42A.




FIG. 42B.




FIG. 42C.

34/35




FIG. 43.




FIG. 44.

35/35




FIG. 45.




FIG. 46.

PCTWORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁶ : C12N 15/87, 15/88, A61K 48/00, 9/127		A3	(11) International Publication Number: WO 96/40964 (43) International Publication Date: 19 December 1996 (19.12.96)
(21) International Application Number: PCT/US96/09949 (22) International Filing Date: 6 June 1996 (06.06.96) (30) Priority Data: 08/484,282 7 June 1995 (07.06.95) US 08/485,458 7 June 1995 (07.06.95) US (71) Applicant (for all designated States except US): INEX PHARMACEUTICALS CORPORATION [CA/CA]; 1779 West 75th Avenue, Vancouver, British Columbia V6P 6P2 (CA). (72) Inventors; and (75) Inventors/Applicants (for US only): WHEELER, Jeffery, J. [US/CA]; 306 - 1340 W. 70th Avenue, Vancouver, British Columbia V6P 2Y8 (CA). BALLY, Marcel, B. [US/CA]; SPC 11 Harding Road, Bowen Island, British Columbia V0N 1G0 (CA). ZHANG, Yuan-Peng [CN/CA]; Suite 105, 40 East 11th Avenue, Vancouver, British Columbia V5T 2B8 (CA). REIMER, Dorothy, L. [US/CA]; Suite 202, 55 East 12th Avenue, Vancouver, British Columbia V5T 4J4 (CA). HOPE, Michael [US/CA]; 3550 West 11th Avenue, Vancouver, British Columbia V6R 2K2 (CA). CULLIS, Pieter, R. [US/CA]; 3732 West 1st Avenue, Vancouver, British Columbia V6R 1H4 (CA). SCHERRER, Peter [US/CA]; Apartment 301, 2664 Birch Street, Vancouver, British Columbia V6H 2T5 (CA).			(74) Agents: KEZER, William, B. et al.; Townsend and Townsend and Crew L.L.P., Two Embarcadero Center, San Francisco, CA 94111-3834 (US). (81) Designated States: AL, AM, AT, AU, AZ, BB, BG, BR, BY, CA, CH, CN, CZ, DE, DK, EE, ES, FI, GB, GE, HU, IL, IS, JP, KE, KG, KP, KR, KZ, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, TJ, TM, TR, TT, UA, UG, US, UZ, VN, ARIPO patent (KE, LS, MW, SD, SZ, UG), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).
			Published <i>With international search report.</i> <i>Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.</i> (88) Date of publication of the international search report: 24 April 1997 (24.04.97)
(54) Title: LIPID-NUCLEIC ACID PARTICLES PREPARED VIA A HYDROPHOBIC LIPID-NUCLEIC ACID COMPLEX INTER-MEDIATE AND USE FOR GENE TRANSFER			
(57) Abstract <p>Novel lipid-nucleic acid particulate complexes which are useful for <i>in vitro</i> or <i>in vivo</i> gene transfer are described. The particles can be formed using either detergent dialysis methods or methods which utilize organic solvents. Upon removal of a solubilizing component (i.e., detergent or an organic solvent) the lipid-nucleic acid complexes form particles wherein the nucleic acid is serum-stable and is protected from degradation. The particles thus formed have access to extravascular sites and target cell populations and are suitable for the therapeutic delivery of nucleic acids.</p>			

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AM	Armenia	GB	United Kingdom	MW	Malawi
AT	Austria	GE	Georgia	MX	Mexico
AU	Australia	GN	Guinea	NE	Niger
BB	Barbados	GR	Greece	NL	Netherlands
BE	Belgium	HU	Hungary	NO	Norway
BF	Burkina Faso	IE	Ireland	NZ	New Zealand
BG	Bulgaria	IT	Italy	PL	Poland
BJ	Benin	JP	Japan	PT	Portugal
BR	Brazil	KE	Kenya	RO	Romania
BY	Belarus	KG	Kyrgyzstan	RU	Russian Federation
CA	Canada	KP	Democratic People's Republic of Korea	SD	Sudan
CF	Central African Republic	KR	Republic of Korea	SE	Sweden
CG	Congo	KZ	Kazakhstan	SG	Singapore
CH	Switzerland	LI	Liechtenstein	SI	Slovenia
CI	Côte d'Ivoire	LK	Sri Lanka	SK	Slovakia
CM	Cameroon	LR	Liberia	SN	Senegal
CN	China	LT	Lithuania	SZ	Swaziland
CS	Czechoslovakia	LU	Luxembourg	TD	Chad
CZ	Czech Republic	LV	Latvia	TG	Togo
DE	Germany	MC	Monaco	TJ	Tajikistan
DK	Denmark	MD	Republic of Moldova	TT	Trinidad and Tobago
EE	Estonia	MG	Madagascar	UA	Ukraine
ES	Spain	ML	Mali	UG	Uganda
FI	Finland	MN	Mongolia	US	United States of America
FR	France	MR	Mauritania	UZ	Uzbekistan
GA	Gabon			VN	Viet Nam

INTERNATIONAL SEARCH REPORT

Int. Application No.

PCT/US 96/09949

A. CLASSIFICATION OF SUBJECT MATTER
IPC 6 C12N15/87 C12N15/88 A61K48/00 A61K9/127

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 6 C12N A61K

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	WO 93 12756 A (UNIV CALIFORNIA) 8 July 1993	1,2,12, 14-17, 19-24, 26,27, 34,35,38
Y	see the whole document	29-31, 33,39
X	US 5 279 833 A (ROSE JOHN K) 18 January 1994	1,2,4,5, 7,10,18
Y	cited in the application see the whole document	29-31, 33,39
X	WO 95 02698 A (LIFE TECHNOLOGIES INC) 26 January 1995 see the whole document	1,2

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

- *A* document defining the general state of the art which is not considered to be of particular relevance
- *E* earlier document but published on or after the international filing date
- *L* document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- *O* document referring to an oral disclosure, use, exhibition or other means
- *P* document published prior to the international filing date but later than the priority date claimed

T later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

X document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

Y document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

A document member of the same patent family

Date of the actual completion of the international search

7 November 1996

Date of mailing of the international search report

21.03.97

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax (+31-70) 340-3016

Authorized officer

Hix, R

INTERNATIONAL SEARCH REPORT

Int. Patent Application No.

PCT/US 96/09949

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P,X	<p>WO 96 10390 A (INEX PHARMACEUTICALS CORP)</p> <p>11 April 1996</p> <p>see the whole document</p> <p style="text-align: center;">-----</p>	1-3

INTERNATIONAL SEARCH REPORT

international application No.

PCT/US 96/09949

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:
2. ☐ Claims Nos.:
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:
3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

see continuation-sheet

1. ☐ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.
2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:
4. ☒ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:
1-7, 10, 12-27, 29-35, 38, 39 (partially) and 8, 9, 11, 28, 36, 37, 40, 41 (completely)

Remark on Protest

- ☐ The additional search fees were accompanied by the applicant's protest.
- ☐ No protest accompanied the payment of additional search fees.

INTERNATIONAL SEARCH REPORT

International Application No. PCT/US 96/09949

FURTHER INFORMATION CONTINUED FROM PCT/ISA/210

- 1.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) and Claims 8, 9, 11, 28, 36, 37, 40 and 41 (completely) : Lipid-nucleic acid complexes comprising DODAC as the cationic lipid and methods of preparation using a detergent or organic solvent based system.
- 2.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) : Lipid-nucleic acid complexes comprising DDAB as the cationic lipid and methods of preparation using a detergent or organic solvent based system.
- 3.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) : Lipid-nucleic acid complexes comprising DOTMA as the cationic lipid and methods of preparation using a detergent or organic solvent based system.
- 4.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) : Lipid-nucleic acid complexes comprising DOSPA as the cationic lipid and methods of preparation using a detergent or organic solvent based system.
- 5.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) : Lipid-nucleic acid complexes comprising DMRIE as the cationic lipid and methods of preparation using a detergent or organic solvent based system.
- 6.) Claims 1-7, 10, 12 to 27, 29 to 35, 38 and 39 (partially) : 6.) Lipid-nucleic acid complexes comprising DOGS as the cationic lipid and methods of preparation using a detergent or organic solvent based system.

INTERNATIONAL SEARCH REPORT

Information on patent family members

Int. J. Application No
PCT/US 96/09949

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 9312756 A	08-07-93	AU 3329193 A	28-07-93
		AU 3467193 A	19-07-93
		CA 2126101 A	24-06-93
		CA 2126103 A	08-07-93
		EP 0619742 A	19-10-94
		EP 0625207 A	23-11-94
		JP 7502510 T	16-03-95
		JP 7505134 T	08-06-95
		WO 9312240 A	24-06-93

US 5279833 A	18-01-94	WO 9115501 A	17-10-91

WO 9502698 A	26-01-95	US 5578475 A	26-11-96

WO 9610390 A	11-04-96	AU 3559595 A	26-04-96
